

Lake Michigan College FY15-FY20 Facility Condition Assessment Final Report

September 12, 2014

Based on Condition Survey Provided by:



Note: At this time Beckwith Hall opened in July 2014 has not yet been added to the Facility Condition Assessment database.

The FY15-FY20 Facility Condition Assessment will be reposted to the Lake Michigan College website when Beckwith Hall has been incorporated into the database.

Lake Michigan College FY15-FY20 Facility Condition Assessment Final Report Outline

| Section 1 | Executive Summary |
|-----------|-------------------|
| | |

Section 2 Summary of Findings

- 3.1 Funding Needs by Asset
- **3.2** Funding Scenarios

Section 3 Requirement List Reports

- **4.1 Critical Requirements**
- **4.2** Complete Listing of Requirements



Executive Portfolio Summary

By Region



Report Overview


This report provides a high-level overview of the portfolio's condition, summarizing key information and identifying areas of concern. This report helps make high-level portfolio management and budget allocation decisions.

The three sections of this report are:

- Portfolio FCI Range: Shows minimum, maximum and group-average facility conditions based on the FCI. The facilities' average age and the backlog (projected costs associated with the group of facilities over the specified timeframe) are also provided.
- · Distribution of Requirement and Renewal Costs: Shows a segmented roll-up of requirement and renewal costs.
- Investment Summary: Shows requirement and renewal costs broken out by year.

Total FCI: 0.180 Portfolio Size: 561,293 SF

Portfolio FCI Range



All costs in 000s USD.






| Region | Minimum FCI | Maximum FCI | FCI Range | Total FCI | Average Age | Backlog |
|-----------------------|-------------|-------------|-----------|-----------|-------------|---------|
| Lake Michigan College | 0.000 | 0.285 | 0.285 | 0.180 | 24.6 | 58,919 |

Distribution of Requirement and Renewal Costs

By Category




| | | I creeminge or |
|-----------------------|----------------|-------------------|
| Category | Estimated Cost | Total Cost |
| Beyond Useful Life | 65,487 | 97% |
| Accessibility | 687 | 1% |
| Grandfathered Code | 510 | 1% |
| Asbestos | 244 | 0% |
| Reliability | 136 | 0% |
| Air and Water Quality | 126 | 0% |
| Capacity/Design | 53 | 0% |
| Life Safety | 3 | 0% |
| Total: | 67,247 | |

Percentage of

All costs in 000s USD.

Investment By Region, Per Year



| Region | 2015 | 2016 | 2017 | 2018 | 2019 | Total |
|-----------------------|--------|-------|-------|--------|--------|--------|
| Lake Michigan College | 21,886 | 5,079 | 6,327 | 23,602 | 10,352 | 67,247 |
| Total: | 21,886 | 5,079 | 6,327 | 23,602 | 10,352 | 67,247 |





Report Parameters:

Region:

Lake Michigan College,

Campus:

Lake Michigan College,

Backlog Period: 5

Costs include 4.70% inflation rate.

Backlog is not inflated.

All costs in 000s USD.



Funding Needs Report

By Asset Name



Region: Lake Michigan College


Campus: Lake Michigan College

Asset: All

Currency: USD Period: 5 years Inflation: 4.70%

The current year is always the Period start date. If "Include past due Action Dates/Renewals" is selected, the cost of those past due Requirements is included in the current year cost.

Summary of Funding Needed by Requirement Type and Year



| Year | Renewal Requirements | Non-Renewal Requirements | Total |
|-------|----------------------|--------------------------|------------|
| 2015 | 20,674,630 | 1,211,656 | 21,886,286 |
| 2016 | 4,531,328 | 547,993 | 5,079,320 |
| 2017 | 6,327,348 | 0 | 6,327,348 |
| 2018 | 23,602,025 | 0 | 23,602,025 |
| 2019 | 10,351,894 | 0 | 10,351,894 |
| Total | 65,487,225 | 1,759,649 | 67,246,874 |



| ear | Region | Campus | Asset | System | Requirement Name | Renewal | Non-Renewal | Total |
|-----|-----------------------|-----------------------|-------------------|----------------------------------------------|--------------------------------------------------------------------|-----------|-------------|-----------|
| 015 | Lake Michigan College | Lake Michigan College | M-TEC | D5039 - Local Area Networks | LAN System - Average Density Renewal | 159,153 | 0 | 159,153 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D5092 - Emergency Light and Power Systems | Emergency Battery Pack Lights Renewal | 49,870 | 0 | 49,870 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D3040 - Distribution Systems | HVAC Cost Study- Engineer Environmental and Efficiency Study | 0 | 63,185 | 63,185 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - C Wing Renewal | 115,057 | 0 | 115,057 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D3030 - Cooling Generating Systems | Chiller - Centrifugal wo Cooling Tower - 1968 Renewal | 250,888 | 0 | 250,888 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D5092 - Emergency Light and Power Systems | Exit Signs, Original - Low Density Renewal | 91,527 | 0 | 91,527 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D3040 - Distribution Systems | HVAC Cost Study- Engineer Environmental and Efficiency Study | 0 | 63,185 | 63,185 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C1020 - Interior Doors | Hardware - Not ADAAG Compliant | 0 | 550,246 | 550,246 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D3040 - Distribution Systems | Perimeter Units Renewal | 5,016,809 | 0 | 5,016,809 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | VAT - S Wing | 0 | 5,791 | 5,791 |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | D5092 - Emergency Light and Power Systems | Emergency Battery Pack Lights Renewal | 29,316 | 0 | 29,316 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | C3030 - Ceiling Finishes | ACT System - 1992 Renewal | 151,556 | 0 | 151,556 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | C10 - Interior Construction | Drain Pipe: Not Insulated | 0 | 1,631 | 1,631 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | C1020 - Interior Doors | Hardware - Not ADAAG Compliant | 0 | 133,786 | 133,786 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - E Wing Renewal | 8,674 | 0 | 8,674 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D5012 - Low Tension Service and Dist. | Electrical Panels - Lack Dedicated Space | 0 | 27,989 | 27,989 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3010 - Wall Finishes | Paint Masonry/Epoxy Finish - Economy Renewal | 68,186 | 0 | 68,186 |
| | Lake Michigan College | Lake Michigan College | M-TEC | D3030 - Cooling Generating Systems | DX Condensing Unit Renewal | 207,396 | 0 | 207,396 |
| | Lake Michigan College | Lake Michigan College | M-TEC | D5092 - Emergency Light and Power Systems | Emergency Battery Pack Lights Renewal | 37,585 | 0 | 37,585 |
| | Lake Michigan College | Lake Michigan College | M-TEC | D3050 - Terminal and Package Units | Unit Heaters - Electric - Garage Renewal | 5,452 | 0 | 5,452 |



| Year | Region | Campus | Asset | System | Requirement Name | Renewal | Non-Renewal | Total |
|------|-----------------------|-----------------------|--------------------------|----------------------------------------------|---------------------------------------------------------------------|-----------|-------------|-----------|
| 2015 | Lake Michigan College | Lake Michigan College | Mendel Center | D3040 - Distribution Systems | Central AHU - Const Volume w/Distribution Renewal | 1,738,330 | 0 | 1,738,330 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D5012 - Low Tension Service and Dist. | Electrical Panels - Lack Dedicated Space | 0 | 37,319 | 37,319 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | B3021 - Glazed Roof Openings | Skylights - Monumental Renewal | 321,601 | 0 | 321,601 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | B2020 - Exterior Windows | Aluminum Windows - L Wing Renewal | 451,048 | 0 | 451,048 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D2020 - Domestic Water Distribution | Heat Exchanger - HW/HW - Shell and Tube Renewal | 4,939 | 0 | 4,939 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D3050 - Terminal and Package Units | Split System AC - 1990 Renewal | 19,850 | 0 | 19,850 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D2020 - Domestic Water Distribution | Water Heater - Gas Renewal | 5,665 | 0 | 5,665 |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | C1035 - Identifying Devices | Fittings: Signage (Room Numbering and Identification) Renewal | 24,489 | 0 | 24,489 |
| | Lake Michigan College | Lake Michigan College | M-TEC | D5037 - Fire Alarm Systems | Fire Alarm System - Average Density Renewal | 205,728 | 0 | 205,728 |
| | Lake Michigan College | Lake Michigan College | M-TEC | D2020 - Domestic Water Distribution | Water Heater - Gas Renewal | 14,009 | 0 | 14,009 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | C3020 - Floor Finishes | Wood Flooring Renewal | 43,441 | 0 | 43,441 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D5021 - Branch Wiring Devices | Electrical Outlets - Lack GFCI Receptacle | 0 | 14,887 | 14,887 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D5092 - Emergency Light and Power Systems | Emergency Battery Pack Lights Renewal | 12,827 | 0 | 12,827 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D2020 - Domestic Water Distribution | Water Heater - Electric Renewal | 7,884 | 0 | 7,884 |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | D5039 - Local Area Networks | LAN System - Average Density Renewal | 124,138 | 0 | 124,138 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D5012 - Low Tension Service and Dist. | Electrical Panel - Lack Circuit Identification | 0 | 3,447 | 3,447 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | C20 - Stairs | Guard and Handrails - Non- Compliant | 0 | 40,558 | 40,558 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D5032 - Intercommunication and Paging System | Intercom System Renewal | 99,117 | 0 | 99,117 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | | Partitions- Generator Room Non-Compliant | 0 | 12,767 | 12,767 |



| Year | Region | Campus | Asset | System | Requirement Name | Renewal | Non-Renewal | Total |
|------|-----------------------|-----------------------|-------------------|-----------------------------------------------|---------------------------------------------------------------|-----------|-------------|-----------|
| 2015 | Lake Michigan College | Lake Michigan College | Mendel Center | D5021 - Branch Wiring Devices | Rooftop HVAC Equipment - Lacks Service Outlets | 0 | 7,910 | 7,910 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - D Wing Lecture Renewal | 65,573 | 0 | 65,573 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D5037 - Fire Alarm Systems | Fire Alarm System - Average Density Renewal | 1,418,921 | 0 | 1,418,921 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D3069 - Other Controls and Instrumentation | Motor Control Center Renewal | 344,370 | 0 | 344,370 |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom Renewal | 126,741 | 0 | 126,741 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D5021 - Branch Wiring Devices | Branch Wiring, Original - Equipment & Devices Renewal | 466,586 | 0 | 466,586 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | C3010 - Wall Finishes | Paint Masonry/Epoxy Finish Renewal | 286,271 | 0 | 286,271 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D3020 - Heat Generating Systems | Boiler HW - Gas/Oil Fired w/Redundancy Renewal | 177,380 | 0 | 177,380 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D2010 - Plumbing Fixtures | Custodial/Utility Sinks Renewal | 158,130 | 0 | 158,130 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D3060 - Controls and Instrumentation | DDC/Pneumatic System - Hybrid Renewal | 1,878,286 | 0 | 1,878,286 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D2030 - Sanitary Waste | Drain Pipe: Not Insulated | 0 | 1,631 | 1,631 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D5092 - Emergency Light and Power Systems | Emergency Generator - Lacks Capacity | 0 | 52,530 | 52,530 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | B2020 - Exterior Windows | Steel Windows Renewal | 649,237 | 0 | 649,237 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | VAT - A Wing | 0 | 996 | 996 |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | C1013 - Retractable Partitions | Folding Partitions Renewal | 28,704 | 0 | 28,704 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D5021 - Branch Wiring Devices | Electrical Outlets - Lack GFCI Receptacle | 0 | 10,319 | 10,319 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | B2010 - Exterior Walls | Brick Walls - Mortar Joints Deteriorated | 0 | 136,350 | 136,350 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - A Wing Renewal | 47,480 | 0 | 47,480 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | B1015 - Exterior Stairs and Fire Escapes | Exterior Stairs - Concrete - Circular Renewal | 25,540 | 0 | 25,540 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D5031 - Public Address and Music Systems | Public Address System - Average Density Renewal | 27,992 | 0 | 27,992 |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | D5037 - Fire Alarm Systems | Fire Alarm System - Average | 160,466 | 0 | 160,466 |



| Year | Region | Campus | Asset | System | Requirement Name | Renewal | Non-Renewal | Total |
|-------|-------------------------|-----------------------|-------------------|----------------------------------------------|------------------------------------------------------------------------|------------|-------------|--------------|
| 2015 | · | , | , | · | Density Renewal | · | , | |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | C3010 - Wall Finishes | Painted Finish - Average (1 Coat Prime - 2 Coats Finish) Renewal | 42,676 | 0 | 42,676 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D5021 - Branch Wiring Devices | Branch Wiring, Original - Equipment & Devices Renewal | 1,018,787 | 0 | 1,018,787 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - L Wing Renewal | 345,007 | 0 | 345,007 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D3040 - Distribution Systems | Central AHU - Const Volume w/Distribution Renewal | 4,138,634 | 0 | 4,138,634 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | | Guards - Lacking | 0 | 26,513 | 26,513 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | | Handrails - Lacking | 0 | 20,615 | 20,615 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | VCT 2 - S Wing Renewal | 3,315 | 0 | 3,315 |
| | | | | | Subtotal for 2015 | 20,674,630 | 1,211,656 | 21,886,286 |
| 2016 | Lake Michigan College | Lake Michigan College | Mendel Center | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - 1992 Renewal | 249,012 | 0 | 249,012 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D5022 - Lighting Equipment | Lighting Fixtures, Original - Average Density Renewal | 412,856 | 0 | 412,856 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | C3010 - Wall Finishes | Wall Covering - Vinyl Renewal | 39,342 | 0 | 39,342 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D5092 - Emergency Light and Power Systems | UPS System 120V Single Phase - per KVA Renewal | 68,320 | 0 | 68,320 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | VAT - C Wing | 0 | 232,965 | 232,965 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - S Wing Renewal | 107,342 | 0 | 107,342 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D1010 - Elevators and Lifts | Hydraulic Freight Elevator Renewal | 243,141 | 0 | 243,141 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D5039 - Local Area Networks | LAN System - Average Density Renewal | 1,149,282 | 0 | 1,149,282 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D3050 - Terminal and Package Units | Unit Heaters - Hot Water Renewal | 36,776 | 0 | 36,776 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | VAT - E Wing | 0 | 4,356 | 4,356 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D5039 - Local Area Networks | LAN System - Average Density Renewal | 525,790 | 0 | 525,790 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D5092 - Emergency Light and Power Systems | Emergency Generator - Average 100KW Renewal | 48,987 | 0 | 48,987 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D1010 - Elevators and Lifts | Hydraulic Passenger Elevator Renewal | 305,695 | 0 | 305,695 |
| ~ · 1 | . (C) 0014 XTTA I AND I | | | | Con 11 2014 1-25-52 DM | | | Daga F of 25 |



| Year | Region | Campus | Asset | System | Requirement Name | Renewal | Non-Renewal | Total |
|------|-----------------------|-----------------------|-------------------|-----------------------------------------------|----------------------------------------------------------|-----------|-------------|-----------|
| 2016 | Lake Michigan College | Lake Michigan College | Mendel Center | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - Hanson Renewal | 27,426 | 0 | 27,426 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3030 - Ceiling Finishes | ACT Concealed Spline System - A Wing Renewal | 66,560 | 0 | 66,560 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C20 - Stairs | Guard and Handrails - Non- Compliant | 0 | 310,671 | 310,671 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - 2006 Renewal | 67,021 | 0 | 67,021 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3030 - Ceiling Finishes | ACT Concealed Spline System - L Wing Renewal | 359,740 | 0 | 359,740 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D2010 - Plumbing Fixtures | Water Coolers - Wall Mount Renewal | 23,108 | 0 | 23,108 |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | D2020 - Domestic Water Distribution | Water Heater - Gas Renewal | 15,316 | 0 | 15,316 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | C1010 - Partitions | Folding Partitions Renewal | 613,724 | 0 | 613,724 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D3069 - Other Controls and Instrumentation | Motor Control Center, Main Elec Room Renewal | 37,953 | 0 | 37,953 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3030 - Ceiling Finishes | ACT Concealed Spline System - D Wing Renewal | 14,296 | 0 | 14,296 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3030 - Ceiling Finishes | ACT Concealed Spline System - S Wing Renewal | 119,641 | 0 | 119,641 |
| | | | | | Subtotal for 2016 | 4,531,328 | 547,993 | 5,079,320 |
| 2017 | Lake Michigan College | Lake Michigan College | Mendel Center | D5092 - Emergency Light and Power Systems | Exit Signs, Original - Low Density Renewal | 65,574 | 0 | 65,574 |
| | Lake Michigan College | Lake Michigan College | South Haven | D5038 - Security and Detection Systems | Security System - Light Density Renewal | 53,487 | 0 | 53,487 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D3020 - Heat Generating Systems | Boiler HW - Gas Fired w/Redundancy Renewal | 1,646,598 | 0 | 1,646,598 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | E - Equipment and Furnishings | Kitchen Equipment Renewal | 127,353 | 0 | 127,353 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D2020 - Domestic Water Distribution | Water Heater - Gas - 2000 Renewal | 15,357 | 0 | 15,357 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D5022 - Lighting Equipment | Lighting Fixtures, Original - Average Density Renewal | 893,280 | 0 | 893,280 |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | D5038 - Security and Detection Systems | Security System - Light Density Renewal | 44,484 | 0 | 44,484 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D3050 - Terminal and Package Units | Unit Heaters - Hot Water Renewal | 19,252 | 0 | 19,252 |



| Year | Region | Campus | Asset | System | Requirement Name | Renewal | Non-Renewal | Total |
|------|-----------------------|-----------------------|-------------------|---------------------------------------------|-------------------------------------------------------------------------------|-----------|-------------|-----------|
| 2017 | Lake Michigan College | Lake Michigan College | Mendel Center | D40 - Fire Protection | Wet Sprinkler System - w/Pump Renewal | 1,351,533 | 0 | 1,351,533 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - B Wing Renewal | 18,066 | 0 | 18,066 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C10 - Interior Construction | Restroom - Complete - Gang - C Wing Renewal | 193,324 | 0 | 193,324 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | VCT 2 - A Wing Renewal | 606 | 0 | 606 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | VCT 2 - E Wing Renewal | 15,142 | 0 | 15,142 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D3040 - Distribution Systems | Central AHU - VAV System w/Distribution Renewal | 1,207,495 | 0 | 1,207,495 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | E - Equipment and Furnishings | Kitchen Equipment Renewal | 127,353 | 0 | 127,353 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D5031 - Public Address and Music Systems | Scoreboard Single Sided – College/High school Arena (Lower End) Renewal | 4,934 | 0 | 4,934 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D5020 - Lighting and Branch Wiring | Lighting - Exterior Renewal | 8,053 | 0 | 8,053 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D5022 - Lighting Equipment | Lighting Fixtures, 1992 Renovation - Average Density Renewal | 313,675 | 0 | 313,675 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | VCT 2 - C Wing Renewal | 88,763 | 0 | 88,763 |
| | Lake Michigan College | Lake Michigan College | M-TEC | D5038 - Security and Detection Systems | Security System - Light Density Renewal | 57,031 | 0 | 57,031 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | C3020 - Floor Finishes | Access Office Flooring System - 1992 Renewal | 35,351 | 0 | 35,351 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D1090 - Other Conveying Systems | Dumbwaiter for Low Rise Renewal | 40,637 | 0 | 40,637 |
| | | | | | Subtotal for 2017 | 6,327,348 | 0 | 6,327,348 |
| 2018 | Lake Michigan College | Lake Michigan College | Bertrand Crossing | D3040 - Distribution Systems | Return Air Ductwork and Fan Renewal | 345,175 | 0 | 345,175 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | C1035 - Identifying Devices | Fittings: Signage (Room Numbering and Identification) Renewal | 113,702 | 0 | 113,702 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - D Wing - 2000 Renewal | 24,390 | 0 | 24,390 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D2030 - Sanitary Waste | Sanitary Waste Renewal | 2,285,100 | 0 | 2,285,100 |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | D3030 - Cooling Generating Systems | Chiller - Screw Renewal | 298,618 | 0 | 298,618 |



| Year | Region | Campus | Asset | System | Requirement Name | Renewal | Non-Renewal | Total |
|------|-----------------------|-----------------------|--------------------------|---------------------------------------|----------------------------------------------------------------------------------------------------|-----------|-------------|--------------|
| 2018 | Lake Michigan College | Lake Michigan College | M-TEC | C3010 - Wall Finishes | Painted Finish - (1 Coat Prime - 2 Coats Finish) Renewal | 89,128 | 0 | 89,128 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | B2020 - Exterior Windows | Aluminum Windows Renewal | 379,633 | 0 | 379,633 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | C3010 - Wall Finishes | Painted Finish - (1 Coat Prime - 2 Coats Finish) Renewal | 123,869 | 0 | 123,869 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | C10 - Interior Construction | Restroom - Complete - Gang Renewal | 202,410 | 0 | 202,410 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C1010 - Partitions | CMU Walls - Glazed 2 Sides Renewal | 52,087 | 0 | 52,087 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D5012 - Low Tension Service and Dist. | Distribution Equipment, Panelboards, and Feeders 13 - 4000A 480Y/277V & 208Y/120V Renewal | 1,540,830 | 0 | 1,540,830 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C1010 - Partitions | Plaster Walls - 3 Coats Renewal | 1,346,767 | 0 | 1,346,767 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | Quarry Tile - L Wing Renewal | 84,093 | 0 | 84,093 |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | D3040 - Distribution Systems | Exhaust System - Restroom w/Roof Fan Renewal | 19,368 | 0 | 19,368 |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | D5022 - Lighting Equipment | Lighting Fixtures - Average Density Renewal | 193,058 | 0 | 193,058 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | C10 - Interior Construction | Restroom - Complete - Double Renewal | 59,642 | 0 | 59,642 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | E - Equipment and Furnishings | Theater And Stage Equipment - Economy Renewal | 309,864 | 0 | 309,864 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | E - Equipment and Furnishings | Fixed Theater Seating - Deluxe - D Wing Renewal | 18,569 | 0 | 18,569 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | E - Equipment and Furnishings | Fixed Theater Seating - Deluxe - S Wing Renewal | 2,487 | 0 | 2,487 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C1010 - Partitions | GWB Walls - Standard (Non- Painted) Renewal | 566,175 | 0 | 566,175 |
| | Lake Michigan College | Lake Michigan College | South Haven | C3010 - Wall Finishes | Painted Finish - (1 Coat Prime - 2 Coats Finish) Renewal | 83,591 | 0 | 83,591 |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | C3030 - Ceiling Finishes | ACT System Renewal | 102,331 | 0 | 102,331 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | C10 - Interior Construction | Restroom - Shower Renewal | 147,866 | 0 | 147,866 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - A Wing - 2000 Renewal | 61,722 | 0 | 61,722 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - B Wing - 2000 | 255,249 | 0 | 255,249 |
| a | | | | | Cop 11 2014 1:25:52 DM | | | Daga 9 of 25 |



| Year | Region | Campus | Asset | System | Requirement Name | Renewal | Non-Renewal | Total |
|------|-----------------------|-----------------------|--------------------------|------------------------------------------|--------------------------------------------------------------|-----------|-------------|--------------|
| 2018 | | | | | Renewal | | | |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D3040 - Distribution Systems | Exhaust System - Kitchen Renewal | 67,705 | 0 | 67,705 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | B1015 - Exterior Stairs and Fire Escapes | Exterior Stairs - Concrete - Platform Renewal | 31,890 | 0 | 31,890 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D2090 - Other Plumbing Systems | Natural Gas Supply for Bldg Renewal | 747,650 | 0 | 747,650 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | B2010 - Exterior Walls | Pedestrian Sky Bridges - Concrete Renewal | 1,039,248 | 0 | 1,039,248 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D40 - Fire Protection | Wet Standpipe System Renewal | 700,657 | 0 | 700,657 |
| | Lake Michigan College | Lake Michigan College | South Haven | D5039 - Local Area Networks | LAN System - Average Density Renewal | 171,315 | 0 | 171,315 |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | C3020 - Floor Finishes | VCT 2 Renewal | 75,464 | 0 | 75,464 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C1010 - Partitions | CMU Block Walls - Plain Renewal | 131,976 | 0 | 131,976 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3030 - Ceiling Finishes | GWB Taped and Finished - D Wing Renewal | 28,664 | 0 | 28,664 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3010 - Wall Finishes | Painted Finish - (1 Coat Prime - 2 Coats Finish) Renewal | 585,714 | 0 | 585,714 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C10 - Interior Construction | Restroom - Complete - Double - A Wing Renewal | 59,642 | 0 | 59,642 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C10 - Interior Construction | Restroom - Complete - Gang - L Wing Renewal | 202,410 | 0 | 202,410 |
| | Lake Michigan College | Lake Michigan College | South Haven | D3050 - Terminal and Package Units | Unit Heaters - Electric Renewal | 31,286 | 0 | 31,286 |
| | Lake Michigan College | Lake Michigan College | South Haven | D2020 - Domestic Water Distribution | Water Heater - Gas Renewal | 32,157 | 0 | 32,157 |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | D3060 - Controls and Instrumentation | DDC System Renewal | 121,963 | 0 | 121,963 |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | D2010 - Plumbing Fixtures | Water Coolers - Wall Mount Wheelchair Type Renewal | 9,900 | 0 | 9,900 |
| | Lake Michigan College | Lake Michigan College | M-TEC | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom Renewal | 236,653 | 0 | 236,653 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D3060 - Controls and Instrumentation | DDC/Pneumatic System - Hybrid Renewal | 986,251 | 0 | 986,251 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - C Wing - 2000 Renewal | 160,038 | 0 | 160,038 |
| | | | | | Kenewal | | | Daga O of 25 |



| Year | Region | Campus | Asset | System | Requirement Name | Renewal | Non-Renewal | Total |
|------|-----------------------|-----------------------|-------------------|----------------------------------------------|--------------------------------------------------------------|-----------|-------------|-----------|
| 2018 | Lake Michigan College | Lake Michigan College | Napier Academic | B2030 - Exterior Doors | Door Assembly - 6 x 7 HM Renewal | 26,950 | 0 | 26,950 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | B2030 - Exterior Doors | Door Assembly - 6 x 7 Storefront Renewal | 138,610 | 0 | 138,610 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | B1015 - Exterior Stairs and Fire Escapes | Exterior Stairs - Concrete Renewal | 29,849 | 0 | 29,849 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D3040 - Distribution Systems | Four Pipe Distribution System w/Pump Renewal | 6,752,945 | 0 | 6,752,945 |
| | Lake Michigan College | Lake Michigan College | South Haven | C3020 - Floor Finishes | Carpeting 5 - Carpet Tiles Renewal | 176,422 | 0 | 176,422 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D3040 - Distribution Systems | Exhaust System - Restroom w/Roof Fan Renewal | 78,349 | 0 | 78,349 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | C10 - Interior Construction | Restroom - Complete - Single Renewal | 53,049 | 0 | 53,049 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - C Wing - 2008 Renewal | 23,892 | 0 | 23,892 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3030 - Ceiling Finishes | GWB Taped and Finished - L Wing Renewal | 6,097 | 0 | 6,097 |
| | Lake Michigan College | Lake Michigan College | South Haven | D3030 - Cooling Generating Systems | DX Condensing Unit Renewal | 223,244 | 0 | 223,244 |
| | Lake Michigan College | Lake Michigan College | South Haven | D5037 - Fire Alarm Systems | Fire Alarm System - Average Density Renewal | 221,449 | 0 | 221,449 |
| | Lake Michigan College | Lake Michigan College | South Haven | C3010 - Wall Finishes | Paint Masonry/Epoxy Finish - Economy Renewal | 15,255 | 0 | 15,255 |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | D5092 - Emergency Light and Power Systems | Exit Signs - Low Density Renewal | 16,971 | 0 | 16,971 |
| | Lake Michigan College | Lake Michigan College | Bertrand Crossing | D5020 - Lighting and Branch Wiring | Lighting - Exterior - HID Wall Packs Renewal | 1,383 | 0 | 1,383 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D3040 - Distribution Systems | Exhaust System - General Building Renewal | 185,740 | 0 | 185,740 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D2090 - Other Plumbing Systems | Natural Gas Supply for Bldg Renewal | 342,045 | 0 | 342,045 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | G2040 - Site Development | Retaining Walls - Concrete Renewal | 114,296 | 0 | 114,296 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - B Wing - 2008 Renewal | 17,919 | 0 | 17,919 |



| Year | Region | Campus | Asset | System | Requirement Name | Renewal | Non-Renewal | Total |
|------|-----------------------|-----------------------|-----------------|----------------------------------------------|----------------------------------------------------------------------------------------------------|------------|-------------|------------|
| 2018 | Lake Michigan College | Lake Michigan College | Napier Academic | B2030 - Exterior Doors | Door Assembly - 3 x 7 HM Renewal | 77,999 | 0 | 77,999 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | B2030 - Exterior Doors | Door Assembly - 3 x 7 Storefront Renewal | 32,988 | 0 | 32,988 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | B2030 - Exterior Doors | Overhead Doors (Manually Operated) - B Wing Renewal | 25,029 | 0 | 25,029 |
| | Lake Michigan College | Lake Michigan College | Napier Academic | D2040 - Rain Water Drainage | Roof Drainage Renewal | 737,485 | 0 | 737,485 |
| | Lake Michigan College | Lake Michigan College | South Haven | C1010 - Partitions | Folding Partitions Renewal | 137,203 | 0 | 137,203 |
| | Lake Michigan College | Lake Michigan College | South Haven | C3020 - Floor Finishes | Vinyl Sheet Goods Renewal | 40,547 | 0 | 40,547 |
| | | | | | Subtotal for 2018 | 23,602,025 | 0 | 23,602,025 |
| 2019 | Lake Michigan College | Lake Michigan College | Mendel Center | B2030 - Exterior Doors | Door Assembly - 6 x 7 Storefront Renewal | 108,844 | 0 | 108,844 |
| | Lake Michigan College | Lake Michigan College | South Haven | C1035 - Identifying Devices | Fittings: Signage (Room Numbering and Identification) Renewal | 35,384 | 0 | 35,384 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | B2030 - Exterior Doors | Door Assembly - 3 x 7 Storefront Renewal | 5,756 | 0 | 5,756 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D5092 - Emergency Light and Power Systems | Emergency Generator - Average 280KW Renewal | 148,186 | 0 | 148,186 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | E - Equipment and Furnishings | Theater And Stage Equipment - High Quality - 1992 Renewal | 5,478,400 | 0 | 5,478,400 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | C3020 - Floor Finishes | VCT 2 Renewal | 86,315 | 0 | 86,315 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | B2030 - Exterior Doors | Door Assembly - 3 x 7 HM Renewal | 19,215 | 0 | 19,215 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | B2030 - Exterior Doors | Door Assembly - 6 x 7 HM Renewal | 47,028 | 0 | 47,028 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D3040 - Distribution Systems | Four Pipe Distribution System w/Pump Renewal | 3,234,637 | 0 | 3,234,637 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | B3020 - Roof Openings | Smoke Hatches Renewal | 97,168 | 0 | 97,168 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D2020 - Domestic Water Distribution | Water Dist Complete Renewal | 576,235 | 0 | 576,235 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D5012 - Low Tension Service and Dist. | Distribution Equipment, Panelboards, and Feeders 13 - 3000A 480Y/277V & 208Y/120V Renewal | 427,692 | 0 | 427,692 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D40 - Fire Protection | Dry Sprinkler System Renewal | 36,611 | 0 | 36,611 |
| | Lake Michigan College | Lake Michigan College | Mendel Center | B2030 - Exterior Doors | Overhead Doors (Electrically | 6,757 | 0 | 6,757 |



| Year | Region | Campus | Asset | System | Requirement Name | Renewal | Non-Renewal | Total |
|------|-----------------------|-----------------------|---------------|---------------------------|---------------------------------------|------------|-------------|------------|
| 2019 | | , | , | , | Operated) Renewal | , | , | |
| | Lake Michigan College | Lake Michigan College | Mendel Center | D2010 - Plumbing Fixtures | Water Coolers - Wall Mount Renewal | 43,666 | 0 | 43,666 |
| | | | | | Subtotal for 2019 | 10,351,894 | 0 | 10,351,894 |
| | | | | | Total | 65.487.225 | 1.759.649 | 67.246.874 |




Region: Lake Michigan College Asset: Napier Academic Campus: Lake Michigan College Asset Number: 1

Report is grouped by Year Currency: USD

| Address 1 | 2755 East Napier Avenue | Address 2 | - |
|-----------|-------------------------|-----------------------|----|
| City | - | State/Province/Region | MI |
| Country | - | ZIP | - |

Current Replacement Value 57,831,793 Size 303,147 SF

Summary of Funding Needed by Requirement Type and Year



| Year | Renewal Requirements | Non-Renewal Requirements | Total |
|-------|----------------------|--------------------------|------------|
| 2015 | 16,352,006 | 900,734 | 17,252,740 |
| 2016 | 2,542,888 | 547,993 | 3,090,881 |
| 2017 | 1,382,105 | 0 | 1,382,105 |
| 2018 | 17,862,828 | 0 | 17,862,828 |
| Total | 38,139,827 | 1,448,727 | 39,588,554 |

| Year | System | Requirement Name | Renewal | Non- Renewal | Total |
|------|-------------------------------------|-------------------------------------------------|---------|-----------------|---------|
| 2015 | D3020 - Heat Generating Systems | Boiler HW - Gas/Oil Fired w/Redundancy Renewal | 177,380 | 0 | 177,380 |
| | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - A Wing Renewal | 47,480 | 0 | 47,480 |
| | D2010 - Plumbing Fixtures | Custodial/Utility Sinks Renewal | 158,130 | 0 | 158,130 |
| | B2020 - Exterior Windows | Steel Windows Renewal | 649,237 | 0 | 649,237 |
| | C3020 - Floor Finishes | VCT 2 - S Wing Renewal | 3,315 | 0 | 3,315 |
| | D2020 - Domestic Water Distribution | Water Heater - Electric Renewal | 7,884 | 0 | 7,884 |
| | B2010 - Exterior Walls | Brick Walls - Mortar Joints Deteriorated | 0 | 136,350 | 136,350 |



| System | Requirement Name | Renewal | Non- Renewal | Total |
|-----------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|
| D3050 - Terminal and Package Units | Split System AC - 1990 Renewal | 19,850 | 0 | 19,850 |
| D5021 - Branch Wiring Devices | Branch Wiring, Original - Equipment & Devices Renewal | 1,018,787 | 0 | 1,018,787 |
| C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - C Wing Renewal | 115,057 | 0 | 115,057 |
| D2030 - Sanitary Waste | Drain Pipe: Not Insulated | 0 | 1,631 | 1,631 |
| D5092 - Emergency Light and Power Systems | Emergency Battery Pack Lights Renewal | 12,827 | 0 | 12,827 |
| D5092 - Emergency Light and Power Systems | Emergency Generator - Lacks Capacity | 0 | 52,530 | 52,530 |
| D3030 - Cooling Generating Systems | Chiller - Centrifugal wo Cooling Tower - 1968 Renewal | 250,888 | 0 | 250,888 |
| D2020 - Domestic Water Distribution | Water Heater - Gas Renewal | 5,665 | 0 | 5,665 |
| B2020 - Exterior Windows | Aluminum Windows - L Wing Renewal | 451,048 | 0 | 451,048 |
| D3060 - Controls and Instrumentation | DDC/Pneumatic System - Hybrid Renewal | 1,878,286 | 0 | 1,878,286 |
| D5012 - Low Tension Service and Dist. | Electrical Panels - Lack Dedicated Space | 0 | 27,989 | 27,989 |
| D5092 - Emergency Light and Power Systems | Exit Signs, Original - Low Density Renewal | 91,527 | 0 | 91,527 |
| D5037 - Fire Alarm Systems | Fire Alarm System - Average Density Renewal | 1,418,921 | 0 | 1,418,921 |
| C1020 - Interior Doors | Hardware - Not ADAAG Compliant | 0 | 550,246 | 550,246 |
| D2020 - Domestic Water Distribution | Heat Exchanger - HW/HW - Shell and Tube Renewal | 4,939 | 0 | 4,939 |
| C3010 - Wall Finishes | Paint Masonry/Epoxy Finish - Economy Renewal | 68,186 | 0 | 68,186 |
| D3040 - Distribution Systems | Perimeter Units Renewal | 5,016,809 | 0 | 5,016,809 |
| C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - D Wing Lecture Renewal | 65,573 | 0 | 65,573 |
| D3040 - Distribution Systems | Central AHU - Const Volume w/Distribution Renewal | 4,138,634 | 0 | 4,138,634 |
| D5021 - Branch Wiring Devices | Electrical Outlets - Lack GFCI Receptacle | 0 | 14,887 | 14,887 |
| B1015 - Exterior Stairs and Fire Escapes | Exterior Stairs - Concrete - Circular Renewal | 25,540 | 0 | 25,540 |
| | Guards - Lacking | 0 | 26,513 | 26,513 |
| D3040 - Distribution Systems | HVAC Cost Study- Engineer Environmental and Efficiency Study | 0 | 63,185 | 63,185 |
| C3020 - Floor Finishes | VAT - S Wing | 0 | 5,791 | 5,791 |
| C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - E Wing Renewal | 8,674 | 0 | 8,674 |
| C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - L Wing Renewal | 345,007 | 0 | 345,007 |
| | Handrails - Lacking | 0 | 20,615 | 20,615 |
| D3069 - Other Controls and Instrumentation | Motor Control Center Renewal | 344,370 | 0 | 344,370 |
| D5031 - Public Address and Music Systems | Public Address System - Average Density Renewal | 27,992 | 0 | 27,992 |
| C3020 - Floor Finishes | VAT - A Wing | 0 | 996 | 996 |
| | | Subtotal for 2015 16,352,006 | 900,734 | 17,252,740 |
| D1010 - Elevators and Lifts | Hydraulic Passenger Elevator Renewal | 305,695 | 0 | 305,695 |
| D5092 - Emergency Light and Power Systems | Emergency Generator - Average 100KW Renewal | 48,987 | 0 | 48,987 |
| D1010 - Elevators and Lifts | Hydraulic Freight Elevator Renewal | 243,141 | 0 | 243,141 |
| C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - S Wing Renewal | 107,342 | 0 | 107,342 |
| D5039 - Local Area Networks | LAN System - Average Density Renewal | 1,149,282 | 0 | 1,149,282 |
| C3030 - Ceiling Finishes | ACT Concealed Spline System - D Wing Renewal | 14,296 | 0 | 14,296 |
| C3020 - Floor Finishes | VAT - E Wing | 0 | 4,356 | 4,356 |
| C3030 - Ceiling Finishes | ACT Concealed Spline System - L Wing Renewal | 359,740 | 0 | 359,740 |
| C3030 - Ceiling Finishes | ACT Concealed Spline System - A Wing Renewal | 66,560 | 0 | 66,560 |
| C3030 - Ceiling Finishes | ACT Concealed Spline System - S Wing Renewal | 119,641 | 0 | 119,641 |
| | D3050 - Terminal and Package Units D5021 - Branch Wiring Devices C3020 - Floor Finishes D2030 - Sanitary Waste D5092 - Emergency Light and Power Systems D5092 - Emergency Light and Power Systems D3030 - Cooling Generating Systems D3030 - Cooling Generating Systems D2020 - Domestic Water Distribution B2020 - Exterior Windows D3060 - Controls and Instrumentation D5012 - Low Tension Service and Dist. D5092 - Emergency Light and Power Systems D5037 - Fire Alarm Systems C1020 - Interior Doors D2020 - Domestic Water Distribution C3010 - Wall Finishes D3040 - Distribution Systems C3020 - Floor Finishes D3040 - Distribution Systems D5021 - Branch Wiring Devices B1015 - Exterior Stairs and Fire Escapes D3040 - Distribution Systems C3020 - Floor Finishes D3069 - Other Controls and Instrumentation D5031 - Public Address and Music Systems C3020 - Floor Finishes D3069 - Other Controls and Lifts D5092 - Emergency Light and Power Systems D1010 - Elevators and Lifts C3020 - Floor Finishes D3030 - Ceiling Finishes C3030 - Ceiling Finishes C3030 - Ceiling Finishes C3030 - Ceiling Finishes C3030 - Ceiling Finishes | D3090 - Terminal and Package Units D5021 - Branch Wiring Devices Branch Wiring, Original - Equipment & Devices Renewal C3020 - Floor Finishes Carpeting 3 - Carpet Broadloom - C Wing Renewal D5092 - Emergency Light and Power Systems D5092 - Emergency Light and Power Systems D5092 - Emergency Light and Power Systems D3030 - Cooling Generating Systems Chiller - Centrifugal wo Cooling Tower - 1968 Renewal D2020 - Domestic Water Distribution B2020 - Exterior Windows Aluminum Windows - L Wing Renewal D3060 - Controls and Instrumentation D5012 - Low Tension Service and Dist. D5092 - Emergency Light and Power Systems D5093 - Fire Alarm Systems D5094 - Fire Alarm Systems Fire Alarm System - Average Density Renewal D3040 - Distribution Systems Fire Alarm System - Average Density Renewal D3040 - Distribution Systems Paint Masoomy/Epoxy Brish - Economy Renewal D3040 - Distribution Systems Paint Masoomy/Epoxy Brish - Economy Renewal D3040 - Distribution Systems Carpeting 3 - Carpet Broadloom - D Wing Lecture Renewal C3020 - Floor Finishes Carpeting 3 - Carpet Broadloom - D Wing Lecture Renewal Cadards - Lack DeCil Constribution Renewal Cadards - Lack GFGI Receptacle B1015 - Exterior Stairs and Fire Escapes B1015 - Exterior Stairs and Fire Escapes B1030 - Color Finishes VAT - S Wing C3020 - Floor Finishes Carpeting 3 - Carpet Broadloom - E Wing Renewal HAAC Cost Study - Engineer Environmental and Efficiency Study VAT - S Wing C3020 - Floor Finishes VAT - A Wing D3030 - Color Finishes VAT - A Wing D1010 - Bevators and Lifts Hydraulic Passenger Elevator Renewal Emergency Generator - Average Density Renewal Systems C3020 - Floor Finishes Carpeting 3 - Carpet Broadloom - S Wing Renewal Landrails - Lacking Motor Control Center Renewal Emergency Generator - Average Density Renewal Systems C3020 - Floor Finishes Carpeting 3 - Carpet Broadloom - S Wing Renewal Landrails - Lacking Motor Control Center Renewal Emergency Generator - Average Density Renewal Landrails - Lacking Lacking D1010 - Bevators and Lifts Hydraulic Freight Elevato | 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 1905000 190500 190500 190500 190500 190500 190500 1905000 190500 190500 190500 190500 190500 190500 1905000 190500 190500 190500 190500 190500 190500 1905000 190500 190500 190500 190500 190500 190500 1905000 190500 190500 190500 190500 190500 190500 1905000 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 1905000 190500 190500 190500 190500 190500 190500 1905000 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 190500 19 | |



| D2010 - Plumbing Fixtures | W. G. L. W.D. J. | | | |
|---------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | Water Coolers - Wall Mount Renewal | 23,108 | 0 | 23,108 |
| C20 - Stairs | Guard and Handrails - Non-Compliant | 0 | 310,671 | 310,671 |
| C3020 - Floor Finishes | VAT - C Wing | 0 | 232,965 | 232,965 |
| D3050 - Terminal and Package Units | Unit Heaters - Hot Water Renewal | 36,776 | 0 | 36,776 |
| D5092 - Emergency Light and Power Systems | UPS System 120V Single Phase - per KVA Renewal | 68,320 | 0 | 68,320 |
| | Subtotal for 2016 | 2,542,888 | 547,993 | 3,090,881 |
| • • • • • • • • • • • • • • • • • • • • | • • | | | 127,353 |
| | | | | 893,280 |
| | · · | | | 606 |
| | | | | 193,324 |
| | | | | 40,637 |
| | | 18,066 | 0 | 18,066 |
| | VCT 2 - C Wing Renewal | 88,763 | 0 | 88,763 |
| C3020 - Floor Finishes | VCT 2 - E Wing Renewal | 15,142 | 0 | 15,142 |
| D5031 - Public Address and Music Systems | Scoreboard Single Sided – College/High school Arena (Lower End) Renewal | 4,934 | 0 | 4,934 |
| | Subtotal for 2017 | 1,382,105 | 0 | 1,382,105 |
| C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - B Wing - 2008 Renewal | 17,919 | 0 | 17,919 |
| C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - C Wing - 2000 Renewal | 160,038 | 0 | 160,038 |
| B2030 - Exterior Doors | Door Assembly - 3 x 7 HM Renewal | 77,999 | 0 | 77,999 |
| D3040 - Distribution Systems | Exhaust System - Kitchen Renewal | 67,705 | 0 | 67,705 |
| C1010 - Partitions | CMU Block Walls - Plain Renewal | 131,976 | 0 | 131,976 |
| C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - A Wing - 2000 Renewal | 61,722 | 0 | 61,722 |
| C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - C Wing - 2008 Renewal | 23,892 | 0 | 23,892 |
| E - Equipment and Furnishings | Fixed Theater Seating - Deluxe - S Wing Renewal | 2,487 | 0 | 2,487 |
| D2090 - Other Plumbing Systems | Natural Gas Supply for Bldg Renewal | 747,650 | 0 | 747,650 |
| C1010 - Partitions | GWB Walls - Standard (Non-Painted) Renewal | 566,175 | 0 | 566,175 |
| B2030 - Exterior Doors | Door Assembly - 3 x 7 Storefront Renewal | 32,988 | 0 | 32,988 |
| C1010 - Partitions | CMU Walls - Glazed 2 Sides Renewal | 52,087 | 0 | 52,087 |
| C3020 - Floor Finishes | Quarry Tile - L Wing Renewal | 84,093 | 0 | 84,093 |
| C3030 - Ceiling Finishes | GWB Taped and Finished - D Wing Renewal | 28,664 | 0 | 28,664 |
| B2030 - Exterior Doors | Door Assembly - 6 x 7 Storefront Renewal | 138,610 | 0 | 138,610 |
| D40 - Fire Protection | Wet Standpipe System Renewal | 700,657 | 0 | 700,657 |
| D2040 - Rain Water Drainage | Roof Drainage Renewal | 737,485 | 0 | 737,485 |
| C10 - Interior Construction | Restroom - Complete - Gang - L Wing Renewal | 202,410 | 0 | 202,410 |
| C3010 - Wall Finishes | Painted Finish - (1 Coat Prime - 2 Coats Finish) Renewal | 585,714 | 0 | 585,714 |
| D5012 - Low Tension Service and Dist. | Distribution Equipment, Panelboards, and Feeders 13 - $4000\mathrm{A}\ 480\mathrm{Y}/277\mathrm{V}\ \&\ 208\mathrm{Y}/120\mathrm{V}$ Renewal | 1,540,830 | 0 | 1,540,830 |
| C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - D Wing - 2000 Renewal | 24,390 | 0 | 24,390 |
| C10 - Interior Construction | Restroom - Complete - Double - A Wing Renewal | 59,642 | 0 | 59,642 |
| B2010 - Exterior Walls | Pedestrian Sky Bridges - Concrete Renewal | 1,039,248 | 0 | 1,039,248 |
| B2030 - Exterior Doors | Overhead Doors (Manually Operated) - B Wing Renewal | 25,029 | 0 | 25,029 |
| D3040 - Distribution Systems | Four Pipe Distribution System w/Pump Renewal | 6,752,945 | 0 | 6,752,945 |
| C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - B Wing - 2000 Renewal | 255,249 | 0 | 255,249 |
| E - Equipment and Furnishings | Fixed Theater Seating - Deluxe - D Wing Renewal | 18,569 | 0 | 18,569 |
| | D3050 - Terminal and Package Units D5092 - Emergency Light and Power Systems E - Equipment and Furnishings D5022 - Lighting Equipment C3020 - Floor Finishes C10 - Interior Construction D1090 - Other Conveying Systems C3020 - Floor Finishes C3020 - Floor Finishes C3020 - Floor Finishes D5031 - Public Address and Music Systems C3020 - Floor Finishes E2030 - Exterior Doors D3040 - Distribution Systems C1010 - Partitions C3020 - Floor Finishes E - Equipment and Furnishings D2090 - Other Plumbing Systems C1010 - Partitions B2030 - Exterior Doors C1010 - Partitions C3020 - Floor Finishes C3030 - Ceiling Finishes C3030 - Ceiling Finishes B2030 - Exterior Doors D40 - Fire Protection D2040 - Rain Water Drainage C10 - Interior Construction C3010 - Wall Finishes D5012 - Low Tension Service and Dist. C3020 - Floor Finishes C10 - Interior Construction B2010 - Exterior Walls B2030 - Exterior Doors D3040 - Distribution Systems C3020 - Floor Finishes | DS090 - Terminal and Package Units Unit Heaters - Hot Water Renewal DS092 - Emergency Light and Power Systems USS System 120V Single Phase - per KVA Renewal Subtotal for 2016 E - Equipment and Furnishings Kitchen Equipment Renewal D5022 - Lighting Equipment Lighting Factures, Original - Average Density Renewal D5022 - Lighting Equipment Lighting Factures, Original - Average Density Renewal C10 - Interior Construction Restroom - Complete - Gang - C Wing Renewal C3020 - Hoor Finishes Carpeting 3 - Carpet Broadloom - B Wing Renewal C3020 - Hoor Finishes VCT 2 - C Wing Renewal C3020 - Hoor Finishes VCT 2 - C Wing Renewal Subtotal for 2017 C3020 - Hoor Finishes VCT 2 - C Wing Renewal Subtotal For 2017 C3020 - Hoor Finishes CT2 - E Wing Renewal Subtotal for 2017 Subtotal for 2017 C3020 - Hoor Finishes Carpeting 3 - Carpet Broadloom - C Wing - 2000 Renewal C3020 - Hoor Finishes Carpeting 3 - Carpet Broadloom - C Wing - 2000 Renewal C3020 - Hoor Finishes Carpeting 3 - Carpet Broadloom - C Wing - 2000 Renewal </td <td> 1900 Terminal and Package Units 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 </td> <td> Dispos - Terminal and Pickage Units Util Heaters - Hor Water Renewal 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908</td> | 1900 Terminal and Package Units 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 1978 | Dispos - Terminal and Pickage Units Util Heaters - Hor Water Renewal 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 1908 |



| Year | System | Requirement Name | Renewa | l Non- Renewal | Total |
|------|------------------------------------------|-----------------------------------------------|-----------------------------|-------------------|------------|
| 2018 | B1015 - Exterior Stairs and Fire Escapes | Exterior Stairs - Concrete Renewal | 29,84 | 0 | 29,849 |
| | B1015 - Exterior Stairs and Fire Escapes | Exterior Stairs - Concrete - Platform Renewal | 31,890 | 0 | 31,890 |
| | B2030 - Exterior Doors | Door Assembly - 6 x 7 HM Renewal | 26,950 | 0 | 26,950 |
| | D2030 - Sanitary Waste | Sanitary Waste Renewal | 2,285,100 | 0 | 2,285,100 |
| | C3030 - Ceiling Finishes | GWB Taped and Finished - L Wing Renewal | 6,09 | 0 | 6,097 |
| | C1010 - Partitions | Plaster Walls - 3 Coats Renewal | 1,346,76 | 0 | 1,346,767 |
| | | | Subtotal for 2018 17,862,82 | 0 | 17,862,828 |
| | | | Total 38.139.82 | 1.448.727 | 39.588.554 |



Region: Lake Michigan College

Asset: Bertrand Crossing

Campus: Lake Michigan College

Asset Number: 2

Report is grouped by Year

Currency: USD

| Address 1 | 1905 Foundation Drive | Address 2 | - |
|-----------|-----------------------|-----------------------|----|
| City | - | State/Province/Region | MI |
| Country | - | ZIP | - |


Current Replacement Value

7,227,363

Size

34,283 SF

Summary of Funding Needed by Requirement Type and Year



| Year | Renewal Requirements | Non-Renewal Requirements | Total |
|-------|----------------------|--------------------------|-----------|
| 2015 | 536,529 | 0 | 536,529 |
| 2016 | 15,316 | 0 | 15,316 |
| 2017 | 44,484 | 0 | 44,484 |
| 2018 | 1,184,231 | 0 | 1,184,231 |
| Total | 1,780,559 | 0 | 1,780,559 |

| Year | System | Requirement Name | Renewal | Non-Renewal | Total |
|------|-------------------------------------------|------------------------------------------------------------------|---------|-------------|---------|
| 2015 | D5037 - Fire Alarm Systems | Fire Alarm System - Average Density Renewal | 160,466 | 0 | 160,466 |
| | D5039 - Local Area Networks | LAN System - Average Density Renewal | 124,138 | 0 | 124,138 |
| | C1013 - Retractable Partitions | Folding Partitions Renewal | 28,704 | 0 | 28,704 |
| | C1035 - Identifying Devices | Fittings: Signage (Room Numbering and Identification) Renewal | 24,489 | 0 | 24,489 |
| | D5092 - Emergency Light and Power Systems | Emergency Battery Pack Lights Renewal | 29,316 | 0 | 29,316 |
| | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom Renewal | 126,741 | 0 | 126,741 |
| | C3010 - Wall Finishes | Painted Finish - Average (1 Coat Prime - 2 Coats Finish) Renewal | 42,676 | 0 | 42,676 |
| | | Subtotal for 2015 | 536,529 | 0 | 536,529 |



| Year | System | Requirement Name | Renewal | Non-Renewal | Total |
|------|-------------------------------------------|----------------------------------------------------|-----------|-------------|-----------|
| 2016 | D2020 - Domestic Water Distribution | Water Heater - Gas Renewal | 15,316 | 0 | 15,316 |
| | | Subtotal for 2016 | 15,316 | 0 | 15,316 |
| 2017 | D5038 - Security and Detection Systems | Security System - Light Density Renewal | 44,484 | 0 | 44,484 |
| | | Subtotal for 2017 | 44,484 | 0 | 44,484 |
| 2018 | D2010 - Plumbing Fixtures | Water Coolers - Wall Mount Wheelchair Type Renewal | 9,900 | 0 | 9,900 |
| | C3020 - Floor Finishes | VCT 2 Renewal | 75,464 | 0 | 75,464 |
| | D3030 - Cooling Generating Systems | Chiller - Screw Renewal | 298,618 | 0 | 298,618 |
| | D3040 - Distribution Systems | Return Air Ductwork and Fan Renewal | 345,175 | 0 | 345,175 |
| | D3040 - Distribution Systems | Exhaust System - Restroom w/Roof Fan Renewal | 19,368 | 0 | 19,368 |
| | D5022 - Lighting Equipment | Lighting Fixtures - Average Density Renewal | 193,058 | 0 | 193,058 |
| | D5092 - Emergency Light and Power Systems | Exit Signs - Low Density Renewal | 16,971 | 0 | 16,971 |
| | C3030 - Ceiling Finishes | ACT System Renewal | 102,331 | 0 | 102,331 |
| | D3060 - Controls and Instrumentation | DDC System Renewal | 121,963 | 0 | 121,963 |
| | D5020 - Lighting and Branch Wiring | Lighting - Exterior - HID Wall Packs Renewal | 1,383 | 0 | 1,383 |
| | | Subtotal for 2018 | 1,184,231 | 0 | 1,184,231 |
| | | Total | 1,780,559 | 0 | 1,780,559 |




Region: Lake Michigan College Asset: Mendel Center
Campus: Lake Michigan College Asset Number: 3

Report is grouped by Year Currency: USD

| Address 1 | 2755 East Napier Avenue | Address 2 | - |
|-----------|-------------------------|-----------------------|----|
| City | - | State/Province/Region | MI |
| Country | - | ZIP | - |

Current Replacement Value 34,096,713 Size 138,688 SF

Summary of Funding Needed by Requirement Type and Year



| Year | Renewal Requirements | Non-Renewal Requirements | Total |
|-------|----------------------|--------------------------|------------|
| 2015 | 3,156,772 | 310,922 | 3,467,695 |
| 2016 | 1,973,124 | 0 | 1,973,124 |
| 2017 | 4,790,241 | 0 | 4,790,241 |
| 2018 | 3,096,715 | 0 | 3,096,715 |
| 2019 | 10,316,510 | 0 | 10,316,510 |
| Total | 23,333,363 | 310,922 | 23,644,285 |

| Year | System | Requirement Name | Renewal | Non- Renewal | Total |
|------|---------------------------------------|--------------------------------------------------------------|---------|-----------------|---------|
| 2015 | D5012 - Low Tension Service and Dist. | Electrical Panels - Lack Dedicated Space | 0 | 37,319 | 37,319 |
| | C3030 - Ceiling Finishes | ACT System - 1992 Renewal | 151,556 | 0 | 151,556 |
| | C10 - Interior Construction | Drain Pipe: Not Insulated | 0 | 1,631 | 1,631 |
| | D3040 - Distribution Systems | HVAC Cost Study- Engineer Environmental and Efficiency Study | 0 | 63,185 | 63,185 |
| | D5021 - Branch Wiring Devices | Rooftop HVAC Equipment - Lacks Service Outlets | 0 | 7,910 | 7,910 |
| | | Partitions- Generator Room Non-Compliant | 0 | 12,767 | 12,767 |



| 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 | Year | System | Requirement Name | | Renewal | Non- Renewal | Total |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---------------------------------------|---------------------------------------------------------------|-------------------|-----------|-----------------|-----------|
| | 2015 | C1020 - Interior Doors | Hardware - Not ADAAG Compliant | , | 0 | 133,786 | 133,786 |
| Systems | | D5021 - Branch Wiring Devices | Electrical Outlets - Lack GFCI Receptacle | | 0 | 10,319 | 10,319 |
| Cabb | | 0 0 | Emergency Battery Pack Lights Renewal | | 49,870 | 0 | 49,870 |
| C20 - Stairs | | D5021 - Branch Wiring Devices | Branch Wiring, Original - Equipment & Devices Renewal | | 466,586 | 0 | 466,586 |
| | | C3020 - Floor Finishes | Wood Flooring Renewal | | 43,441 | 0 | 43,441 |
| System | | C20 - Stairs | Guard and Handrails - Non-Compliant | | 0 | 40,558 | 40,558 |
| Same | | 0 0 | Intercom System Renewal | | 99,117 | 0 | 99,117 |
| B3021 - Glazed Roof Openings Skylights - Monumental Renewal 321.61 30 31.60 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 31.47 | | D3040 - Distribution Systems | Central AHU - Const Volume w/Distribution Renewal | | 1,738,330 | 0 | 1,738,330 |
| | | C3010 - Wall Finishes | Paint Masonry/Epoxy Finish Renewal | | 286,271 | 0 | 286,271 |
| 1988 1988 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 1989 | | B3021 - Glazed Roof Openings | Skylights - Monumental Renewal | | 321,601 | 0 | 321,601 |
| 2016 D3069 - Other Controls and Instrumentation 18795 18795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 28795 | | D5012 - Low Tension Service and Dist. | Electrical Panel - Lack Circuit Identification | | 0 | 3,447 | 3,447 |
| Instrumentation | | | | Subtotal for 2015 | 3,156,772 | 310,922 | 3,467,695 |
| Califor Wall Finishes Wall Covering - Vinyl Renewal 39,342 0 613,724 | 2016 | | Motor Control Center, Main Elec Room Renewal | | 37,953 | 0 | 37,953 |
| Califor | | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - 1992 Renewal | | 249,012 | 0 | 249,012 |
| Carpeting 3 - Carpet Broadloom - Hanson Renewal 7.426 0 0.74.26 | | C3010 - Wall Finishes | Wall Covering - Vinyl Renewal | | 39,342 | 0 | 39,342 |
| Carpeting 3 - Carpet Broadloom - 2006 Renewal 67.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.021 0 0 17.0221 0 0 17.0221 0 0 0 0 0 0 0 0 0 | | C1010 - Partitions | Folding Partitions Renewal | | 613,724 | 0 | 613,724 |
| D5022 - Lighting Equipment Lighting Fixtures, Original - Average Density Renewal 12,856 0 412,856 | | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - Hanson Renewal | | 27,426 | 0 | 27,426 |
| 1 | | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom - 2006 Renewal | | 67,021 | 0 | 67,021 |
| Subtolator 2016 | | D5022 - Lighting Equipment | Lighting Fixtures, Original - Average Density Renewal | | 412,856 | 0 | 412,856 |
| 2017 2018 20304 Distribution Systems Central AHU - VAV System w/Distribution Renewal 1,207,495 0 1,207,495 20302 Heat Generating Systems Boiler HW - Gas Fired w/Redundancy Renewal 1,646,598 0 1,646,598 20302 Floor Finishes Access Office Flooring System - 1992 Renewal 35,351 0 35,351 20202 Domestic Water Distribution Water Heater - Gas - 2000 Renewal 15,357 0 65,574 205092 Emergency Light and Power Systems Exit Signs, Original - Low Density Renewal 65,574 0 65,574 205092 Lighting and Branch Wiring Lighting - Exterior Renewal 8,053 0 8,053 205092 Lighting Equipment Lighting - Exterior Renewal 1,361,533 0 127,353 205092 Lighting Equipment Lighting - Exterior Renewal 1,361,533 0 127,353 205092 Lighting Equipment Lighting - Exterior Renewal 1,351,533 0 1,351,533 205092 Lighting Equipment Lighting - Exterior Renewal 1,351,533 0 1,351,533 205093 Lighting Equipment Lighting - Exterior Renewal 1,351,533 0 1,351,533 205094 Lighting - Exterior Renewal 1,351,533 0 1,351,533 205094 Lighting - Lighting - Exterior Renewal 1,351,533 0 1,351,533 205095 Lighting - Light | | D5039 - Local Area Networks | LAN System - Average Density Renewal | | 525,790 | 0 | 525,790 |
| D3020 - Heat Generating Systems Boiler HW - Gas Fired w/Redundancy Renewal 1.646.598 0 1.646.598 C3020 - Floor Finishes Access Office Flooring System - 1992 Renewal 35.351 0 35.351 D2020 - Domestic Water Distribution Water Heater - Gas - 2000 Renewal 15.357 0 5.574 0 5.574 D5092 - Emergency Light and Power Exit Signs, Original - Low Density Renewal 65.574 0 65.574 Systems D5020 - Lighting and Branch Wiring Lighting - Exterior Renewal 8.053 0 8.053 0 5.022 - Lighting Equipment Lighting Fixtures, 1992 Renovation - Average Density Renewal 313.675 0 313.675 E - Equipment and Furnishings Ritchen Equipment Renewal 127.353 0 127.353 D40 - Fire Protection Wet Sprinkler System - w/Pump Renewal 1.351.533 0 1.351.533 D3050 - Terminal and Package Units Unit Heaters - Hot Water Renewal 19.252 0 19.252 D40 - Fire Protection Wet Sprinkler System - w/Pump Renewal 379.633 0 379.633 C3010 - Wall Finishes Painted Finish - (1 Coat Prime - 2 Coats Finish) Renewal 123.869 0 123.869 E - Equipment and Furnishings Theater And Stage Equipment - Economy Renewal 133.665 0 147.866 0 147.866 C1035 - Identifying Devices Fittings: Signage (Room Numbering and Identification) Renewal 113.702 0 113.702 0 113.702 0 113.702 0 113.702 0 113.702 0 113.702 0 113.702 0 113.702 0 113.702 0 113.702 0 113.702 0 113.702 0 113.702 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 113.703 0 1 | | | | Subtotal for 2016 | 1,973,124 | 0 | 1,973,124 |
| C3020 - Floor Finishes | 2017 | D3040 - Distribution Systems | Central AHU - VAV System w/Distribution Renewal | | 1,207,495 | 0 | 1,207,495 |
| D2020 - Domestic Water Distribution Water Heater - Gas - 2000 Renewal 15.357 0 15.357 | | D3020 - Heat Generating Systems | Boiler HW - Gas Fired w/Redundancy Renewal | | 1,646,598 | 0 | 1,646,598 |
| D5092 - Emergency Light and Power Systems Stit Signs, Original - Low Density Renewal 65.574 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8.053 8. | | C3020 - Floor Finishes | Access Office Flooring System - 1992 Renewal | | 35,351 | 0 | 35,351 |
| Systems | | D2020 - Domestic Water Distribution | Water Heater - Gas - 2000 Renewal | | 15,357 | 0 | 15,357 |
| D5022 - Lighting Equipment Lighting Fixtures, 1992 Renovation - Average Density Renewal 313,675 0 313,675 E - Equipment and Furnishings Kitchen Equipment Renewal 127,353 0 127,353 D40 - Fire Protection Wet Sprinkler System - w/Pump Renewal 1,351,533 0 1,351,533 D3050 - Terminal and Package Units Unit Heaters - Hot Water Renewal 19,252 0 19,252 Subtotal for 2017 4,790,241 0 4,790,241 2018 B2020 - Exterior Windows Aluminum Windows Renewal 379,633 0 379,633 C3010 - Wall Finishes Painted Finish - (1 Coat Prime - 2 Coats Finish) Renewal 123,869 0 123,869 E - Equipment and Furnishings Theater And Stage Equipment - Economy Renewal 309,864 0 309,864 C10 - Interior Construction Restroom - Shower Renewal 147,866 0 147,866 C1035 - Identifying Devices Fittings: Signage (Room Numbering and Identification) Renewal 113,702 0 113,702 D3040 - Distribution Systems Exhaust System - Restroom w/Roof Fan Renewal 114,296 0 78,349 G2040 - Site Development Retaining Walls - Concrete Renewal 114,296 0 986,251 C10 - Interior Construction Restroom - Complete - Single Renewal 53,049 0 53,049 D3040 - Distribution Systems Exhaust System - Hybrid Renewal 53,049 0 53,049 D3040 - Distribution Systems Exhaust System - General Building Renewal 185,740 0 185,740 | | 0 0 | Exit Signs, Original - Low Density Renewal | | 65,574 | 0 | 65,574 |
| E - Equipment and Furnishings Kitchen Equipment Renewal 127,353 0 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 127,353 | | D5020 - Lighting and Branch Wiring | Lighting - Exterior Renewal | | 8,053 | 0 | 8,053 |
| D40 - Fire Protection Wet Sprinkler System - w/Pump Renewal 1,351,533 0 1,351,533 D3050 - Terminal and Package Units Unit Heaters - Hot Water Renewal 19,252 0 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 | | D5022 - Lighting Equipment | Lighting Fixtures, 1992 Renovation - Average Density Renewal | | 313,675 | 0 | 313,675 |
| D3050 - Terminal and Package Units Unit Heaters - Hot Water Renewal 19,252 0 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 19,252 | | E - Equipment and Furnishings | Kitchen Equipment Renewal | | 127,353 | 0 | 127,353 |
| 2018 B2020 - Exterior Windows Aluminum Windows Renewal 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,633 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379,635 0 379 | | D40 - Fire Protection | Wet Sprinkler System - w/Pump Renewal | | 1,351,533 | 0 | 1,351,533 |
| 2018 B2020 - Exterior Windows Aluminum Windows Renewal 379,633 0 379,633 C3010 - Wall Finishes Painted Finish - (1 Coat Prime - 2 Coats Finish) Renewal 123,869 0 123,869 E - Equipment and Furnishings Theater And Stage Equipment - Economy Renewal 309,864 0 309,864 C10 - Interior Construction Restroom - Shower Renewal 147,866 0 147,866 C1035 - Identifying Devices Fittings: Signage (Room Numbering and Identification) Renewal 113,702 0 113,702 D3040 - Distribution Systems Exhaust System - Restroom w/Roof Fan Renewal 78,349 0 78,349 G2040 - Site Development Retaining Walls - Concrete Renewal 114,296 0 114,296 D3060 - Controls and Instrumentation DDC/Pneumatic System - Hybrid Renewal 986,251 0 986,251 C10 - Interior Construction Restroom - Complete - Single Renewal 53,049 0 53,049 D3040 - Distribution Systems Exhaust System - General Building Renewal 185,740 0 185,740 | | D3050 - Terminal and Package Units | Unit Heaters - Hot Water Renewal | | 19,252 | 0 | 19,252 |
| C3010 - Wall Finishes Painted Finish - (1 Coat Prime - 2 Coats Finish) Renewal 123,869 0 123,869 E - Equipment and Furnishings Theater And Stage Equipment - Economy Renewal 309,864 0 309,864 C10 - Interior Construction Restroom - Shower Renewal 147,866 0 147,866 C1035 - Identifying Devices Fittings: Signage (Room Numbering and Identification) Renewal 113,702 0 113,702 D3040 - Distribution Systems Exhaust System - Restroom w/Roof Fan Renewal 78,349 0 78,349 G2040 - Site Development Retaining Walls - Concrete Renewal 114,296 0 114,296 D3060 - Controls and Instrumentation DDC/Pneumatic System - Hybrid Renewal 986,251 0 986,251 C10 - Interior Construction Restroom - Complete - Single Renewal 53,049 0 53,049 D3040 - Distribution Systems Exhaust System - General Building Renewal 185,740 0 185,740 | | | | Subtotal for 2017 | 4,790,241 | 0 | 4,790,241 |
| E - Equipment and Furnishings Theater And Stage Equipment - Economy Renewal 309,864 C10 - Interior Construction Restroom - Shower Renewal 147,866 C1035 - Identifying Devices Fittings: Signage (Room Numbering and Identification) Renewal 113,702 0 113,702 D3040 - Distribution Systems Exhaust System - Restroom w/Roof Fan Renewal 78,349 0 78,349 G2040 - Site Development Retaining Walls - Concrete Renewal 114,296 D3060 - Controls and Instrumentation DDC/Pneumatic System - Hybrid Renewal 986,251 C10 - Interior Construction Restroom - Complete - Single Renewal 53,049 0 53,049 D3040 - Distribution Systems Exhaust System - General Building Renewal 185,740 0 185,740 | 2018 | B2020 - Exterior Windows | Aluminum Windows Renewal | | 379,633 | 0 | 379,633 |
| C10 - Interior Construction Restroom - Shower Renewal 147,866 0 147,866 C1035 - Identifying Devices Fittings: Signage (Room Numbering and Identification) Renewal 113,702 0 113,702 D3040 - Distribution Systems Exhaust System - Restroom w/Roof Fan Renewal 78,349 0 78,349 G2040 - Site Development Retaining Walls - Concrete Renewal 114,296 0 114,296 D3060 - Controls and Instrumentation DDC/Pneumatic System - Hybrid Renewal 986,251 0 986,251 C10 - Interior Construction Restroom - Complete - Single Renewal 53,049 0 53,049 D3040 - Distribution Systems Exhaust System - General Building Renewal 185,740 0 185,740 | | C3010 - Wall Finishes | Painted Finish - (1 Coat Prime - 2 Coats Finish) Renewal | | 123,869 | 0 | 123,869 |
| C1035 - Identifying Devices Fittings: Signage (Room Numbering and Identification) Renewal 113,702 0 113,702 D3040 - Distribution Systems Exhaust System - Restroom w/Roof Fan Renewal 78,349 0 78,349 G2040 - Site Development Retaining Walls - Concrete Renewal 114,296 0 114,296 D3060 - Controls and Instrumentation DDC/Pneumatic System - Hybrid Renewal 986,251 0 986,251 C10 - Interior Construction Restroom - Complete - Single Renewal 53,049 0 53,049 D3040 - Distribution Systems Exhaust System - General Building Renewal 185,740 0 185,740 | | E - Equipment and Furnishings | Theater And Stage Equipment - Economy Renewal | | 309,864 | 0 | 309,864 |
| D3040 - Distribution Systems Exhaust System - Restroom w/Roof Fan Renewal 78,349 0 78,349 G2040 - Site Development Retaining Walls - Concrete Renewal 114,296 0 114,296 D3060 - Controls and Instrumentation DDC/Pneumatic System - Hybrid Renewal 986,251 0 986,251 C10 - Interior Construction Restroom - Complete - Single Renewal 53,049 0 53,049 D3040 - Distribution Systems Exhaust System - General Building Renewal 185,740 0 185,740 | | C10 - Interior Construction | Restroom - Shower Renewal | | 147,866 | 0 | 147,866 |
| G2040 - Site DevelopmentRetaining Walls - Concrete Renewal114,2960114,296D3060 - Controls and InstrumentationDDC/Pneumatic System - Hybrid Renewal986,2510986,251C10 - Interior ConstructionRestroom - Complete - Single Renewal53,049053,049D3040 - Distribution SystemsExhaust System - General Building Renewal185,7400185,740 | | C1035 - Identifying Devices | Fittings: Signage (Room Numbering and Identification) Renewal | | 113,702 | 0 | 113,702 |
| D3060 - Controls and Instrumentation DDC/Pneumatic System - Hybrid Renewal 986,251 0 986,251 C10 - Interior Construction Restroom - Complete - Single Renewal 53,049 0 53,049 D3040 - Distribution Systems Exhaust System - General Building Renewal 185,740 0 185,740 | | D3040 - Distribution Systems | Exhaust System - Restroom w/Roof Fan Renewal | | 78,349 | 0 | 78,349 |
| C10 - Interior Construction Restroom - Complete - Single Renewal 53,049 0 53,049 D3040 - Distribution Systems Exhaust System - General Building Renewal 185,740 0 185,740 | | G2040 - Site Development | Retaining Walls - Concrete Renewal | | 114,296 | 0 | 114,296 |
| D3040 - Distribution Systems Exhaust System - General Building Renewal 185,740 0 185,740 | | D3060 - Controls and Instrumentation | DDC/Pneumatic System - Hybrid Renewal | | 986,251 | 0 | 986,251 |
| | | C10 - Interior Construction | Restroom - Complete - Single Renewal | | 53,049 | 0 | 53,049 |
| C10 - Interior Construction Restroom - Complete - Gang Renewal 202,410 0 202,410 | | D3040 - Distribution Systems | Exhaust System - General Building Renewal | | 185,740 | 0 | 185,740 |
| | | C10 - Interior Construction | Restroom - Complete - Gang Renewal | | 202,410 | 0 | 202,410 |



| Year | System | Requirement Name | Renewal | Non- Renewal | Total |
|------|----------------------------------------------|----------------------------------------------------------------------------------------------|------------|-----------------|------------|
| 2018 | C10 - Interior Construction | Restroom - Complete - Double Renewal | 59,642 | 0 | 59,642 |
| | D2090 - Other Plumbing Systems | Natural Gas Supply for Bldg Renewal | 342,045 | 0 | 342,045 |
| | | Subtotal for 2018 | 3,096,715 | 0 | 3,096,715 |
| 2019 | B2030 - Exterior Doors | Overhead Doors (Electrically Operated) Renewal | 6,757 | 0 | 6,757 |
| | B2030 - Exterior Doors | Door Assembly - 6 x 7 Storefront Renewal | 108,844 | 0 | 108,844 |
| | B2030 - Exterior Doors | Door Assembly - 3 x 7 HM Renewal | 19,215 | 0 | 19,215 |
| | D3040 - Distribution Systems | Four Pipe Distribution System w/Pump Renewal | 3,234,637 | 0 | 3,234,637 |
| | D5012 - Low Tension Service and Dist. | Distribution Equipment, Panelboards, and Feeders 13 - 3000A 480Y/277V $\&~208Y/120V$ Renewal | 427,692 | 0 | 427,692 |
| | D5092 - Emergency Light and Power Systems | Emergency Generator - Average 280KW Renewal | 148,186 | 0 | 148,186 |
| | E - Equipment and Furnishings | Theater And Stage Equipment - High Quality - 1992 Renewal | 5,478,400 | 0 | 5,478,400 |
| | B2030 - Exterior Doors | Door Assembly - 3 x 7 Storefront Renewal | 5,756 | 0 | 5,756 |
| | D2010 - Plumbing Fixtures | Water Coolers - Wall Mount Renewal | 43,666 | 0 | 43,666 |
| | D2020 - Domestic Water Distribution | Water Dist Complete Renewal | 576,235 | 0 | 576,235 |
| | B3020 - Roof Openings | Smoke Hatches Renewal | 97,168 | 0 | 97,168 |
| | D40 - Fire Protection | Dry Sprinkler System Renewal | 36,611 | 0 | 36,611 |
| | C3020 - Floor Finishes | VCT 2 Renewal | 86,315 | 0 | 86,315 |
| | B2030 - Exterior Doors | Door Assembly - 6 x 7 HM Renewal | 47,028 | 0 | 47,028 |
| | | Subtotal for 2019 | 10,316,510 | 0 | 10,316,510 |
| | | Total | 23,333,363 | 310,922 | 23,644,285 |




Region: Lake Michigan College Asset: M-TEC
Campus: Lake Michigan College Asset Number: 4

Report is grouped by Year Currency: USD

| Address 1 | 400 Klock Road | Address 2 | - |
|-----------|----------------|-----------------------|----|
| City | - | State/Province/Region | MI |
| Country | - | ZIP | - |

Current Replacement Value 8,562,885 Size 43,953 SF

Summary of Funding Needed by Requirement Type and Year



| Year | Renewal Requirements | Non-Renewal Requirements | Total |
|-------|----------------------|--------------------------|-----------|
| 2015 | 629,322 | 0 | 629,322 |
| 2017 | 57,031 | 0 | 57,031 |
| 2018 | 325,781 | 0 | 325,781 |
| Total | 1,012,134 | 0 | 1,012,134 |

| Year | System | Requirement Name | Renewal | Non-Renewal | Total |
|------|-------------------------------------------|---------------------------------------------|---------|-------------|---------|
| 2015 | D3050 - Terminal and Package Units | Unit Heaters - Electric - Garage Renewal | 5,452 | 0 | 5,452 |
| | D5092 - Emergency Light and Power Systems | Emergency Battery Pack Lights Renewal | 37,585 | 0 | 37,585 |
| | D5039 - Local Area Networks | LAN System - Average Density Renewal | 159,153 | 0 | 159,153 |
| | D3030 - Cooling Generating Systems | DX Condensing Unit Renewal | 207,396 | 0 | 207,396 |
| | D2020 - Domestic Water Distribution | Water Heater - Gas Renewal | 14,009 | 0 | 14,009 |
| | D5037 - Fire Alarm Systems | Fire Alarm System - Average Density Renewal | 205,728 | 0 | 205,728 |
| | | Subtotal for 2015 | 629,322 | 0 | 629,322 |
| 2017 | D5038 - Security and Detection Systems | Security System - Light Density Renewal | 57,031 | 0 | 57,031 |
| | | Subtotal for 2017 | 57,031 | 0 | 57,031 |



| Year | System | Requirement Name | Renewal | Non-Renewal | Total |
|------|------------------------|----------------------------------------------------------|-----------|-------------|-----------|
| 2018 | C3020 - Floor Finishes | Carpeting 3 - Carpet Broadloom Renewal | 236,653 | 0 | 236,653 |
| | C3010 - Wall Finishes | Painted Finish - (1 Coat Prime - 2 Coats Finish) Renewal | 89,128 | 0 | 89,128 |
| | | Subtotal for 2018 | 325,781 | 0 | 325,781 |
| | | Total | 1.012.134 | 0 | 1.012.134 |




Region: Lake Michigan College Asset: South Haven
Campus: Lake Michigan College Asset Number: 5

Report is grouped by Year Currency: USD

| Address 1 | 125 Veterans Boulevard | Address 2 | - |
|-----------|------------------------|-----------------------|----|
| City | - | State/Province/Region | MI |
| Country | - | ZIP | - |

Current Replacement Value 8,727,663 Size 41,222 SF

Summary of Funding Needed by Requirement Type and Year



| Year | Renewal Requirements | Non-Renewal Requirements | Total |
|-------|----------------------|--------------------------|-----------|
| 2017 | 53,487 | 0 | 53,487 |
| 2018 | 1,132,470 | 0 | 1,132,470 |
| 2019 | 35,384 | 0 | 35,384 |
| Total | 1,221,341 | 0 | 1,221,341 |

| Year | System | Requirement Name | Renewal | Non-Renewal | Total |
|------|----------------------------------------|----------------------------------------------------------|---------|-------------|---------|
| 2017 | D5038 - Security and Detection Systems | Security System - Light Density Renewal | 53,487 | 0 | 53,487 |
| | | Subtotal for 2017 | 53,487 | 0 | 53,487 |
| 2018 | D3050 - Terminal and Package Units | Unit Heaters - Electric Renewal | 31,286 | 0 | 31,286 |
| | D2020 - Domestic Water Distribution | Water Heater - Gas Renewal | 32,157 | 0 | 32,157 |
| | D3030 - Cooling Generating Systems | DX Condensing Unit Renewal | 223,244 | 0 | 223,244 |
| | C1010 - Partitions | Folding Partitions Renewal | 137,203 | 0 | 137,203 |
| | D5039 - Local Area Networks | LAN System - Average Density Renewal | 171,315 | 0 | 171,315 |
| | C3010 - Wall Finishes | Painted Finish - (1 Coat Prime - 2 Coats Finish) Renewal | 83,591 | 0 | 83,591 |
| | C3010 - Wall Finishes | Paint Masonry/Epoxy Finish - Economy Renewal | 15,255 | 0 | 15,255 |





| Year | System | Requirement Name | Renewal | Non-Renewal | Total |
|------|-----------------------------|---------------------------------------------------------------|-----------|-------------|-----------|
| 2018 | C3020 - Floor Finishes | Vinyl Sheet Goods Renewal | 40,547 | 0 | 40,547 |
| | D5037 - Fire Alarm Systems | Fire Alarm System - Average Density Renewal | 221,449 | 0 | 221,449 |
| | C3020 - Floor Finishes | Carpeting 5 - Carpet Tiles Renewal | 176,422 | 0 | 176,422 |
| | | Subtotal for 2018 | 1,132,470 | 0 | 1,132,470 |
| 2019 | C1035 - Identifying Devices | Fittings: Signage (Room Numbering and Identification) Renewal | 35,384 | 0 | 35,384 |
| | | Subtotal for 2019 | 35,384 | 0 | 35,384 |
| | | Total | 1,221,341 | 0 | 1,221,341 |




Funding / FCI Report









FCI-Target - Funding to reduce FCI to 5.00% in 5 years

FCI-Specific Annual Funding

Cost Curve Applied: Spiky 0

Note: All cost curves other than Spiky 0 will result in a change to the starting FCI that is displayed. For a full description of all Forecast Parameters applied to this funding scenario, see the final page of this report.

All costs in USD.



Maintain - FCI

Cost Curve Applied: Spiky 0

| • | | | | | | | | Funding | |
|------|------------------|--------------|------------------------------|----------------------------|-------------------|-----------------|-----------|---------|--------|
| Year | Replacement Cost | Renewal Cost | Backlog Deterioration | Total New Liability | New Backlog Total | Net Plant Value | Funding | Reserve | FCI |
| 2014 | 57,831,792 | 5,870,754 | 0 | 6,731,054 | 6,731,054 | 51,100,738 | 0 | 0 | 0.1164 |
| 2015 | 60,549,889 | 6,146,680 | 140,948 | 6,811,021 | 7,047,414 | 53,502,475 | 6,811,021 | 0 | 0.1164 |
| 2016 | 63,395,737 | 6,435,574 | 147,573 | 6,583,147 | 7,378,643 | 56,017,094 | 6,583,147 | 0 | 0.1164 |
| 2017 | 66,375,340 | 6,738,047 | 154,509 | 6,892,555 | 7,725,440 | 58,649,900 | 6,892,555 | 0 | 0.1164 |
| 2018 | 69,494,984 | 7,054,735 | 161,771 | 7,216,506 | 8,088,536 | 61,406,449 | 7,216,506 | 0 | 0.1164 |
| 2019 | 72,761,252 | 7,386,308 | 169,374 | 7,555,682 | 8,468,697 | 64,292,555 | 7,555,682 | 0 | 0.1164 |
| 2020 | 76,181,034 | 7,733,465 | 177,335 | 7,910,799 | 8,866,726 | 67,314,308 | 7,910,799 | 0 | 0.1164 |



Target - Funding to reduce FCI to 5.00% in 5 years

Cost Curve Applied: Spiky 0

| | | | | | | | | Funding | |
|------|------------------|--------------|------------------------------|----------------------------|-------------------|-----------------|-----------|---------|--------|
| Year | Replacement Cost | Renewal Cost | Backlog Deterioration | Total New Liability | New Backlog Total | Net Plant Value | Funding | Reserve | FCI |
| 2014 | 57,831,792 | 5,870,754 | 0 | 6,731,054 | 6,731,054 | 51,100,738 | 0 | 0 | 0.1164 |
| 2015 | 60,549,889 | 6,146,680 | 140,948 | 6,811,021 | 6,243,430 | 54,306,459 | 7,615,005 | 0 | 0.1031 |
| 2016 | 63,395,737 | 6,435,574 | 130,737 | 6,566,312 | 5,695,100 | 57,700,637 | 7,408,083 | 0 | 0.0898 |
| 2017 | 66,375,340 | 6,738,047 | 119,255 | 6,857,302 | 5,081,436 | 61,293,904 | 7,738,636 | 0 | 0.0766 |
| 2018 | 69,494,984 | 7,054,735 | 106,405 | 7,161,140 | 4,397,506 | 65,097,478 | 8,083,898 | 0 | 0.0633 |
| 2019 | 72,761,252 | 7,386,308 | 92,084 | 7,478,392 | 3,638,063 | 69,123,189 | 8,444,519 | 0 | 0.0500 |
| 2020 | 76,181,034 | 7,733,465 | 76,181 | 7,809,646 | 3,809,052 | 72,371,983 | 7,809,646 | 0 | 0.0500 |



Specific Annual Funding

Cost Curve Applied: Spiky 0

| | | | | | | | | Funding | |
|------|------------------|--------------|------------------------------|----------------------------|-------------------|-----------------|-----------|---------|--------|
| Year | Replacement Cost | Renewal Cost | Backlog Deterioration | Total New Liability | New Backlog Total | Net Plant Value | Funding | Reserve | FCI |
| 2014 | 57,831,792 | 5,870,754 | 0 | 6,731,054 | 6,731,054 | 51,100,738 | 0 | 0 | 0.1164 |
| 2015 | 60,549,889 | 6,146,680 | 140,948 | 6,811,021 | 12,811,436 | 47,738,454 | 1,047,000 | 0 | 0.2116 |
| 2016 | 63,395,737 | 6,435,574 | 268,271 | 6,703,846 | 19,021,210 | 44,374,527 | 1,096,209 | 0 | 0.3000 |
| 2017 | 66,375,340 | 6,738,047 | 398,304 | 7,136,351 | 25,903,828 | 40,471,512 | 1,147,731 | 0 | 0.3903 |
| 2018 | 69,494,984 | 7,054,735 | 542,426 | 7,597,161 | 33,516,796 | 35,978,188 | 1,201,674 | 0 | 0.4823 |
| 2019 | 72,761,252 | 7,386,308 | 701,842 | 8,088,150 | 41,922,083 | 30,839,168 | 1,258,153 | 0 | 0.5762 |
| 2020 | 76,181,034 | 7,733,465 | 877,848 | 8,611,313 | 51,186,450 | 24,994,584 | 1,317,286 | 0 | 0.6719 |



Forecast Parameters

Region Lake Michigan College
Campus Lake Michigan College

Asset Napier Academic

Systems All
Priority All
Requirement Category All
Years 6
Inflation 4.70%
Backlog Deterioration 2.00%
Renewal Option Average

Fiscal Year Start Date (mm/dd) 1/1
FCI/RI Setting FCI

Specific-Apply Inflation to Funding True

* About Cost Curves:

Cost curve are models of how renewal costs may occur over time. In the Spiky 0 forecast, all renewal costs are projected to occur entirely in the System Renewal Year. In all other cost curve forecasts, renewal costs are projected to occur over multiple years, including years before and after the System Renewal Year. As a result, the starting Facilities Condition Index (FCI) that is displayed will not be the current FCI, because the model will apply funding prior to the current year.

Spiky 0

For detailed information about cost curves, see "About Cost Curves" in the Funding Module section of the VFA facility User Manual.

Cost curve



Requirement List Report

By Asset Name and Priority

Critical / Potentially Critical



Region Name: Lake Michigan College

Campus Name: Lake Michigan College

Asset Name: Bertrand Crossing-2

Reporting Currency: USD

Prime System : All

Requirement Priority: 2- Potentially Critical

Requirement Category : All

Requirements Included: All

No Data Available



Region Name: Lake Michigan College

Campus Name: Lake Michigan College

Asset Name: M-TEC-4

Reporting Currency: USD

Prime System : All

Requirement Priority: 2- Potentially Critical

Requirement Category : All

Requirements Included: All

No Data Available





Region Name: Lake Michigan College

Campus Name: Lake Michigan College

Asset Name: Mendel Center-3

Reporting Currency: USD

Prime System : All

Requirement Priority: 2- Potentially Critical

Requirement Category : All

Requirements Included: All

| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|-------------------------------|---------------------------------------------------|-------------------------|---------------------------------------------|----------------|--------------|-------------|--------|----------------------------------------------------------------------------------------------------|---------------------|
| 2- Potentially Critical | Electrical Panel - Lack Circuit Identification | Life Safety | D5012 - Low Tension Service and Dist. | 2015 | Aug 29, 2015 | | Open | Distribution Equipment, Panelboards, and Feeders 13, 1992 Renovation - 3000A 480Y/277V & 208Y/120V | 3,292 |
| 2- Potentia | ally Critical | | | | | | | | 3,292 |
| Mendel Ce | enter-3 | | | | | | | | 3,292 |



Region Name: Lake Michigan College

Campus Name: Lake Michigan College

Asset Name: Napier Academic-1

Reporting Currency: USD

Prime System : All

Requirement Priority: 2- Potentially Critical

Requirement Category : All

Requirements Included: All

No Data Available



Region Name: Lake Michigan College

Campus Name: Lake Michigan College

Asset Name: South Haven-5

Reporting Currency: USD

Prime System: All

Requirement Priority: 2- Potentially Critical

Requirement Category : All

Requirements Included: All

No Data Available

Lake Michigan College

Lake Michigan College

Summary

3,292 3,292 3,292



Requirement List Report

By Asset Name and Category





Region Name: Lake Michigan College

Campus Name: Lake Michigan College

Asset Name: Bertrand Crossing-2

Reporting Currency: USD

Prime System: All

Requirement Priority : All

Requirement Category : All

Requirements Included: All

| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------|------------------------------------------------|-------------------------|-------------------------------------------------|----------------|--------------|-------------|--------|----------------------------------------|---------------------|
| 1- Currently Critical | Emergency Battery Pack Lights Renewal | Beyond Useful Life | D5092 - Emergency Light and Power Systems | 2015 | Oct 2, 2015 | | Open | Emergency Battery Pack Lights | 28,000 |
| 1- Currently Cri | tical | | | | | | | | 28,000 |
| 2- Potentially Critical | Fire Alarm System - Average Density Renewal | Beyond Useful Life | D5037 - Fire Alarm Systems | 2015 | Oct 2, 2015 | | Open | Fire Alarm System - Average Density | 153,263 |
| 2- Potentially C | ritical | | | | | | | | 153,263 |
| 3- Necessary - Not Yet Critical | Folding Partitions Renewal | Beyond Useful Life | C1013 - Retractable Partitions | 2015 | Nov 17, 2015 | | Open | Folding Partitions | 27,415 |
| 3- Necessary - Not Yet Critical | ACT System Renewal | Beyond Useful Life | C3030 - Ceiling Finishes | 2018 | Nov 17, 2018 | | Open | ACT System | 85,157 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------|---------------------------------------------------------------------|-------------------------|-------------------------------------------------|----------------|--------------|-------------|--------|-------------------------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | Carpeting 3 - Carpet Broadloom Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2015 | Nov 17, 2015 | | Open | Carpeting 3 - Carpet Broadloom | 121,051 |
| 3- Necessary - Not Yet Critical | Exit Signs - Low Density Renewal | Beyond Useful Life | D5092 - Emergency Light and Power Systems | 2018 | Nov 17, 2018 | | Open | Exit Signs - Low Density | 14,123 |
| 3- Necessary - Not Yet Critical | Chiller - Screw Renewal | Beyond Useful Life | D3030 - Cooling Generating Systems | 2018 | Nov 17, 2018 | | Open | Chiller - Screw | 248,502 |
| 3- Necessary - Not Yet Critical | Exhaust System - Restroom w/Roof Fan Renewal | Beyond Useful Life | D3040 - Distribution Systems | 2018 | Nov 17, 2018 | | Open | Exhaust System - Restroom w/Roof Fan | 16,117 |
| 3- Necessary - Not Yet Critical | Lighting - Exterior - HID Wall Packs Renewal | Beyond Useful Life | D5020 - Lighting and Branch Wiring | 2018 | Nov 17, 2018 | | Open | Lighting - Exterior - HID Wall Packs | 1,151 |
| 3- Necessary - Not Yet Critical | DDC System Renewal | Beyond Useful Life | D3060 - Controls and Instrumentation | 2018 | Nov 17, 2018 | | Open | DDC System | 101,494 |
| 3- Necessary - Not Yet Critical | Water Heater - Gas Renewal | Beyond Useful Life | D2020 - Domestic Water Distribution | 2016 | Nov 17, 2016 | | Open | Water Heater - Gas | 13,971 |
| 3- Necessary - Not Yet Critical | Security System - Light Density Renewal | Beyond Useful Life | D5038 - Security and Detection Systems | 2017 | Nov 17, 2017 | | Open | Security System - Light Density | 38,758 |
| 3- Necessary - Not Yet Critical | Lighting Fixtures - Average Density Renewal | Beyond Useful Life | D5022 - Lighting Equipment | 2018 | Nov 17, 2018 | | Open | Lighting Fixtures - Average Density | 160,658 |
| 3- Necessary - Not Yet Critical | Return Air Ductwork and Fan Renewal | Beyond Useful Life | D3040 - Distribution Systems | 2018 | Nov 17, 2018 | | Open | Return Air Ductwork and Fan | 287,245 |
| 3- Necessary - Not Yet Critical | Painted Finish - Average (1 Coat Prime - 2 Coats Finish) Renewal | Beyond Useful Life | C3010 - Wall Finishes | 2015 | Nov 17, 2015 | | Open | Painted Finish - Average (1 Coat Prime - 2 Coats Finish) | 40,760 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------|---------------------------------------------------------------------|-------------------------|--------------------------------|----------------|--------------|-------------|--------|-------------------------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | Water Coolers - Wall Mount Wheelchair Type Renewal | Beyond Useful Life | D2010 - Plumbing Fixtures | 2018 | Nov 17, 2018 | | Open | Water Coolers - Wall Mount Wheelchair Type | 8,238 |
| 3- Necessary - Not Yet Critical | VCT 2 Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2018 | Nov 17, 2018 | | Open | VCT 2 | 62,799 |
| 3- Necessary - Not Yet Critical | LAN System - Average Density Renewal | Beyond Useful Life | D5039 - Local Area Networks | 2015 | Nov 17, 2015 | | Open | LAN System - Average Density | 118,566 |
| 3- Necessary - Not Yet Critical | Fittings: Signage (Room Numbering and Identification) Renewal | Beyond Useful Life | C1035 - Identifying Devices | 2015 | Nov 17, 2015 | | Open | Fittings: Signage (Room Numbering and Identification) | 23,390 |
| 3- Necessary - N | ot Yet Critical | | | | | | | | 1,369,395 |
| Bertrand Crossin | ıg-2 | | | | | | | | 1,550,658 |





Region Name: Lake Michigan College

Campus Name: Lake Michigan College

Asset Name: M-TEC-4

Reporting Currency: USD

Prime System: All

Requirement Priority : All

Requirement Category : All

Requirements Included: All

| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------|------------------------------------------------|-------------------------|-------------------------------------------|----------------|--------------|-------------|--------|----------------------------------------|---------------------|
| 2- Potentially Critical | Emergency Battery Pack Lights Renewal | Beyond Useful Life | D5092 - Emergency Light and Power Systems | 2015 | Oct 2, 2015 | | Open | Emergency Battery Pack Lights | 35,898 |
| 2- Potentially Critical | Fire Alarm System - Average Density Renewal | Beyond Useful Life | D5037 - Fire Alarm Systems | 2015 | Oct 2, 2015 | | Open | Fire Alarm System - Average Density | 196,493 |
| 2- Potentially Crit | ical | | | | | | | | 232,391 |
| 3- Necessary - Not Yet Critical | LAN System - Average Density Renewal | Beyond Useful Life | D5039 - Local Area Networks | 2015 | Nov 17, 2015 | | Open | LAN System - Average Density | 152,009 |
| 3- Necessary - Not Yet Critical | Carpeting 3 - Carpet Broadloom Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2018 | Sep 3, 2018 | | Open | Carpeting 3 - Carpet Broadloom | 196,936 |
| 3- Necessary - Not Yet Critical | Unit Heaters - Electric - Garage Renewal | Beyond Useful Life | D3050 - Terminal and Package Units | 2015 | Nov 17, 2015 | | Open | Unit Heaters - Electric - Garage | 5,207 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------|----------------------------------------------------------|-------------------------|-------------------------------------------|----------------|--------------|-------------|--------|-----------------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | Security System - Light Density Renewal | Beyond Useful Life | D5038 - Security and Detection Systems | 2017 | Nov 17, 2017 | • | Open | Security System - Light Density | 49,690 |
| 3- Necessary - Not Yet Critical | Painted Finish - (1 Coat Prime - 2 Coats Finish) Renewal | Beyond Useful Life | C3010 - Wall Finishes | 2018 | Sep 3, 2018 | | Open | Painted Finish - (1 Coat Prime - 2 Coats Finish) | 74,170 |
| 3- Necessary - Not Yet Critical | DX Condensing Unit Renewal | Beyond Useful Life | D3030 - Cooling Generating Systems | 2015 | Nov 17, 2015 | | Open | DX Condensing Unit | 198,086 |
| 3- Necessary - Not Yet Critical | Water Heater - Gas Renewal | Beyond Useful Life | D2020 - Domestic Water Distribution | 2015 | Nov 17, 2015 | | Open | Water Heater - Gas | 13,380 |
| 3- Necessary - No | ot Yet Critical | | | | | | | | 689,478 |
| M-TEC-4 | | | | | | | | | 921,869 |





Region Name: Lake Michigan College

Campus Name: Lake Michigan College

Asset Name: Mendel Center-3

Reporting Currency: USD

Prime System: All

Requirement Priority : All

Requirement Category : All

Requirements Included: All

| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|-----------------------------|----------------------------------------------------------|-------------------------|----------------------------------|----------------|-------------|-------------|--------|--------------------------------------------------|---------------------|
| 1- Currently Critical | ACT System - 1992 Renewal | Beyond Useful Life | C3030 - Ceiling Finishes | 2015 | Sep 3, 2015 | | Open | ACT System - 1992 | 144,753 |
| 1- Currently Critical | Branch Wiring, Original - Equipment & Devices Renewal | Beyond Useful Life | D5021 - Branch Wiring Devices | 2015 | Sep 3, 2015 | | Open | Branch Wiring, Original - Equipment & Devices | 445,641 |
| 1- Currently Critical | Skylights - Monumental Renewal | Beyond Useful Life | B3021 - Glazed Roof Openings | 2015 | Oct 2, 2015 | | Open | Skylights - Monumental | 307,164 |
| 1- Currentl | y Critical | | | | | | | | 897,558 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|-------------------------------|----------------------------------------------------------|-------------------------|----------------------------------------------------|----------------|--------------|-------------|--------|----------------------------------------------------------------------------------------------------|---------------------|
| 2- Potentially Critical | Carpeting 3 - Carpet Broadloom - 1992 Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2016 | Sep 3, 2016 | | Open | Carpeting 3 - Carpet Broadloom - 1992 | 227,158 |
| 2- Potentially Critical | Folding Partitions Renewal | Beyond Useful Life | C1010 - Partitions | 2016 | Sep 3, 2016 | | Open | Folding Partitions | 559,860 |
| 2- Potentially Critical | Lighting Fixtures, Original - Average Density Renewal | Beyond Useful Life | D5022 - Lighting Equipment | 2016 | Sep 3, 2016 | | Open | Lighting Fixtures, Original - Average Density | 376,622 |
| 2- Potentially Critical | Carpeting 3 - Carpet Broadloom - Hanson Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2016 | Sep 3, 2016 | | Open | Carpeting 3 - Carpet Broadloom - Hanson | 25,019 |
| 2- Potentially Critical | Intercom System Renewal | Beyond Useful Life | D5032 - Intercommunication and Paging System | 2015 | Oct 2, 2015 | | Open | Intercom System | 94,668 |
| 2- Potentially Critical | Electrical Panel - Lack Circuit Identification | Life Safety | D5012 - Low Tension Service and Dist. | 2015 | Aug 29, 2015 | | Open | Distribution Equipment, Panelboards, and Feeders 13, 1992 Renovation - 3000A 480Y/277V & 208Y/120V | 3,292 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|--------------------------------------------------------------------|--------------------------|-------------------------------------------------|----------------|--------------|-------------|--------|----------------------------------------------|---------------------|
| 2- Potentially Critical | Wall Covering - Vinyl Renewal | Beyond Useful Life | C3010 - Wall Finishes | 2016 | Sep 3, 2016 | | Open | Wall Covering - Vinyl | 35,889 |
| 2- Potentially Critical | Emergency Battery Pack Lights Renewal | Beyond Useful Life | D5092 - Emergency Light and Power Systems | 2015 | Oct 2, 2015 | | Open | Emergency Battery Pack Lights | 47,632 |
| 2- Potentia | lly Critical | | | | | | | | 1,370,140 |
| 3- Necessary - Not Yet Critical | HVAC Cost Study- Engineer Environmental and Efficiency Study | Air and Water Quality | D3040 - Distribution Systems | 2015 | Oct 1, 2015 | | Open | Central AHU - Const Volume w/Distribution | 60,349 |
| 3- Necessary - Not Yet Critical | Central AHU - Const Volume w/Distribution Renewal | Beyond Useful Life | D3040 - Distribution Systems | 2015 | Sep 11, 2015 | | Open | Central AHU - Const Volume w/Distribution | 1,660,296 |
| 3- Necessary - Not Yet Critical | Exhaust System - General Building Renewal | Beyond Useful Life | D3040 - Distribution Systems | 2018 | Oct 2, 2018 | | Open | Exhaust System - General Building | 154,568 |
| 3- Necessary - Not Yet Critical | Restroom - Shower Renewal | Beyond Useful Life | C10 - Interior Construction | 2018 | Sep 3, 2018 | | Open | Restroom - Shower | 123,050 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|--------------------------------------------------------------------|-------------------------|-------------------------------------------------|----------------|--------------|-------------|--------|---------------------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | Restroom - Complete - Single Renewal | Beyond Useful Life | C10 - Interior Construction | 2018 | Sep 3, 2018 | | Open | Restroom - Complete - Single | 44,146 |
| 3- Necessary - Not Yet Critical | Lighting Fixtures, 1992 Renovation - Average Density Renewal | Beyond Useful Life | D5022 - Lighting Equipment | 2017 | Oct 2, 2017 | | Open | Lighting Fixtures, 1992 Renovation - Average Density | 273,300 |
| 3- Necessary - Not Yet Critical | Kitchen Equipment Renewal | Beyond Useful Life | E - Equipment and Furnishings | 2017 | Oct 2, 2017 | | Open | Kitchen Equipment | 110,961 |
| 3- Necessary - Not Yet Critical | Painted Finish - (1 Coat Prime - 2 Coats Finish) Renewal | Beyond Useful Life | C3010 - Wall Finishes | 2018 | Sep 3, 2018 | | Open | Painted Finish - (1 Coat Prime - 2 Coats Finish) | 103,080 |
| 3- Necessary - Not Yet Critical | Retaining Walls - Concrete Renewal | Beyond Useful Life | G2040 - Site Development | 2018 | Nov 17, 2018 | | Open | Retaining Walls - Concrete | 95,114 |
| 3- Necessary - Not Yet Critical | Exit Signs, Original - Low Density Renewal | Beyond Useful Life | D5092 - Emergency Light and Power Systems | 2017 | Oct 2, 2017 | | Open | Exit Signs, Original - Low Density | 57,134 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|-----------------------------------------------|-------------------------|------------------------------------|----------------|--------------|-------------|--------|------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | LAN System - Average Density Renewal | Beyond Useful Life | D5039 - Local Area Networks | 2016 | Nov 17, 2016 | | Open | LAN System - Average Density | 479,644 |
| 3- Necessary - Not Yet Critical | Door Assembly - 6 x 7 HM Renewal | Beyond Useful Life | B2030 - Exterior Doors | 2019 | Oct 2, 2019 | | Open | Door Assembly - 6 x 7 HM | 37,379 |
| 3- Necessary - Not Yet Critical | Wood Flooring Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2015 | Nov 17, 2015 | | Open | Wood Flooring | 41,491 |
| 3- Necessary - Not Yet Critical | Water Coolers - Wall Mount Renewal | Beyond Useful Life | D2010 - Plumbing Fixtures | 2019 | Oct 2, 2019 | | Open | Water Coolers - Wall Mount | 34,707 |
| 3- Necessary - Not Yet Critical | Boiler HW - Gas Fired w/Redundancy Renewal | Beyond Useful Life | D3020 - Heat Generating Systems | 2017 | Oct 2, 2017 | | Open | Boiler HW - Gas Fired w/Redundancy | 1,434,655 |
| 3- Necessary - Not Yet Critical | Aluminum Windows Renewal | Beyond Useful Life | B2020 - Exterior Windows | 2018 | Oct 2, 2018 | | Open | Aluminum Windows | 315,920 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|-------------------------------------------------|-------------------------|---------------------------------------|----------------|--------------|-------------|--------|--------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | Smoke Hatches Renewal | Beyond Useful Life | B3020 - Roof Openings | 2019 | Oct 2, 2019 | | Open | Smoke Hatches | 77,230 |
| 3- Necessary - Not Yet Critical | Lighting - Exterior Renewal | Beyond Useful Life | D5020 - Lighting and Branch Wiring | 2017 | Oct 2, 2017 | | Open | Lighting - Exterior | 7,017 |
| 3- Necessary - Not Yet Critical | Unit Heaters - Hot Water Renewal | Beyond Useful Life | D3050 - Terminal and Package Units | 2017 | Nov 17, 2017 | | Open | Unit Heaters - Hot Water | 16,774 |
| 3- Necessary - Not Yet Critical | Door Assembly - 3 x 7 Storefront Renewal | Beyond Useful Life | B2030 - Exterior Doors | 2019 | Oct 2, 2019 | | Open | Door Assembly - 3 x 7 Storefront | 4,575 |
| 3- Necessary - Not Yet Critical | Door Assembly - 6 x 7 Storefront Renewal | Beyond Useful Life | B2030 - Exterior Doors | 2019 | Oct 2, 2019 | | Open | Door Assembly - 6 x 7 Storefront | 86,511 |
| 3- Necessary - Not Yet Critical | Access Office Flooring System - 1992 Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2017 | Nov 17, 2017 | | Open | Access Office Flooring System - 1992 | 30,800 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|-------------------------------------------------------------------------------------------|-------------------------|--------------------------------------------------|----------------|-------------|-------------|--------|-----------------------------------------------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | Dry Sprinkler System Renewal | Beyond Useful Life | D40 - Fire Protection | 2019 | Oct 2, 2019 | | Open | Dry Sprinkler System | 29,099 |
| 3- Necessary - Not Yet Critical | Emergency Generator - Average 280KW Renewal | Beyond Useful Life | D5092 - Emergency Light and Power Systems | 2019 | Oct 2, 2019 | | Open | Emergency Generator - Average 280KW | 117,781 |
| 3- Necessary - Not Yet Critical | Motor Control Center, Main Elec Room Renewal | Beyond Useful Life | D3069 - Other Controls and Instrumentation | 2016 | Oct 2, 2016 | | Open | Motor Control Center, Main Elec Room | 34,622 |
| 3- Necessary - Not Yet Critical | DDC/Pneumatic System - Hybrid Renewal | Beyond Useful Life | D3060 - Controls and Instrumentation | 2018 | Oct 2, 2018 | | Open | DDC/Pneumatic System - Hybrid | 820,731 |
| 3- Necessary - Not Yet Critical | Distribution Equipment, Panelboards, and Feeders 13 - 3000A 480Y/277V & 208Y/120V Renewal | Beyond Useful Life | D5012 - Low Tension Service and Dist. | 2019 | Oct 2, 2019 | | Open | Distribution Equipment, Panelboards, and Feeders 13 - 3000A 480Y/277V & 208Y/120V | 339,937 |
| 3- Necessary - Not Yet Critical | Wet Sprinkler System - w/Pump Renewal | Beyond Useful Life | D40 - Fire Protection | 2017 | Oct 2, 2017 | | Open | Wet Sprinkler System - w/Pump | 1,177,570 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|---------------------------------------------------------------------|-------------------------|----------------------------------------|----------------|--------------|-------------|--------|-------------------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | Water Dist Complete Renewal | Beyond Useful Life | D2020 - Domestic Water Distribution | 2019 | Oct 2, 2019 | • | Open | Water Dist Complete | 458,000 |
| 3- Necessary - Not Yet Critical | Theater And Stage Equipment - Economy Renewal | Beyond Useful Life | E - Equipment and Furnishings | 2018 | Sep 3, 2018 | | Open | Theater And Stage Equipment - Economy | 257,860 |
| 3- Necessary - Not Yet Critical | Natural Gas Supply for Bldg Renewal | Beyond Useful Life | D2090 - Other Plumbing Systems | 2018 | Oct 2, 2018 | | Open | Natural Gas Supply for Bldg | 284,641 |
| 3- Necessary - Not Yet Critical | Central AHU - VAV System w/Distribution Renewal | Beyond Useful Life | D3040 - Distribution Systems | 2017 | Nov 17, 2017 | | Open | Central AHU - VAV System w/Distribution | 1,052,072 |
| 3- Necessary - Not Yet Critical | Four Pipe Distribution System w/Pump Renewal | Beyond Useful Life | D3040 - Distribution Systems | 2019 | Oct 2, 2019 | | Open | Four Pipe Distribution System w/Pump | 2,570,941 |
| 3- Necessary - Not Yet Critical | Fittings: Signage (Room Numbering and Identification) Renewal | Beyond Useful Life | C1035 - Identifying Devices | 2018 | Oct 2, 2018 | | Open | Fittings: Signage (Room Numbering and Identification) | 94,620 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|--------------------------------------------------------------|-------------------------|----------------------------------------|----------------|--------------|-------------|--------|------------------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | Exhaust System - Restroom w/Roof Fan Renewal | Beyond Useful Life | D3040 - Distribution Systems | 2018 | Oct 2, 2018 | | Open | Exhaust System - Restroom w/Roof Fan | 65,200 |
| 3- Necessary - Not Yet Critical | Paint Masonry/Epoxy Finish Renewal | Beyond Useful Life | C3010 - Wall Finishes | 2015 | Nov 17, 2015 | | Open | Paint Masonry/Epoxy Finish | 273,420 |
| 3- Necessary - Not Yet Critical | Restroom - Complete - Gang Renewal | Beyond Useful Life | C10 - Interior Construction | 2018 | Sep 3, 2018 | | Open | Restroom - Complete - Gang | 168,440 |
| 3- Necessary - Not Yet Critical | Door Assembly - 3 x 7 HM Renewal | Beyond Useful Life | B2030 - Exterior Doors | 2019 | Oct 2, 2019 | | Open | Door Assembly - 3 x 7 HM | 15,273 |
| 3- Necessary - Not Yet Critical | Water Heater - Gas - 2000 Renewal | Beyond Useful Life | D2020 - Domestic Water Distribution | 2017 | Oct 2, 2017 | | Open | Water Heater - Gas - 2000 | 13,380 |
| 3- Necessary - Not Yet Critical | Theater And Stage Equipment - High Quality - 1992 Renewal | Beyond Useful Life | E - Equipment and Furnishings | 2019 | Oct 2, 2019 | | Open | Theater And Stage Equipment - High Quality - 1992 | 4,354,320 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|---------------------------------------------------|-------------------------|--------------------------------|----------------|--------------|-------------|--------|----------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | Carpeting 3 - Carpet Broadloom - 2006 Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2016 | Nov 17, 2016 | | Open | Carpeting 3 - Carpet Broadloom - 2006 | 61,139 |
| 3- Necessary - Not Yet Critical | VCT 2 Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2019 | Oct 2, 2019 | | Open | VCT 2 | 68,604 |
| 3- Necessary - Not Yet Critical | Restroom - Complete - Double Renewal | Beyond Useful Life | C10 - Interior Construction | 2018 | Sep 3, 2018 | | Open | Restroom - Complete - Double | 49,632 |
| 3- Necessary - Not Yet Critical | Drain Pipe: Not Insulated | Accessibility | C10 - Interior Construction | 2015 | Oct 1, 2015 | | Open | Restroom - Complete - Gang | 1,558 |
| 3- Necessary - Not Yet Critical | Overhead Doors (Electrically Operated) Renewal | Beyond Useful Life | B2030 - Exterior Doors | 2019 | Oct 2, 2019 | | Open | Overhead Doors (Electrically Operated) | 5,370 |
| 3- Necessar | ry - Not Yet Critical | | | | | | | | 17,562,911 |
| Not Time Critical | Guard and Handrails - Non- Compliant | Grandfathered Code | C20 - Stairs | 2015 | Oct 1, 2015 | | Open | Stairs | 38,737 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|----------------------|---------------------------------------------------|-------------------------|---------------------------------------------|----------------|-------------|-------------|--------|-----------------------------------------------------------------------------------|---------------------|
| Not Time Critical | Hardware - Not ADAAG Compliant | Accessibility | C1020 - Interior Doors | 2015 | Oct 1, 2015 | | Open | Swinging Doors | 127,780 |
| Not Time Critical | Electrical Outlets - Lack GFCI Receptacle | Grandfathered Code | D5021 - Branch Wiring Devices | 2015 | Oct 1, 2015 | | Open | Branch Wiring, Original - Equipment & Devices | 9,856 |
| Not Time Critical | Rooftop HVAC Equipment - Lacks Service Outlets | Grandfathered Code | D5021 - Branch Wiring Devices | 2015 | Oct 1, 2015 | | Open | Branch Wiring, Original - Equipment & Devices | 7,555 |
| Not Time Critical | Partitions- Generator Room Non- Compliant | Grandfathered Code | | 2015 | Oct 1, 2015 | | Open | | 12,194 |
| Not Time Critical | Electrical Panels - Lack Dedicated Space | Grandfathered Code | D5012 - Low Tension Service and Dist. | 2015 | Oct 1, 2015 | | Open | Distribution Equipment, Panelboards, and Feeders 13 - 3000A 480Y/277V & 208Y/120V | 35,644 |
| Not Time (| Critical | | | | | | | | 231,766 |
| Mendel Ce | enter-3 | | | | | | | | 20,062,375 |





Region Name: Lake Michigan College

Campus Name: Lake Michigan College

Asset Name: Napier Academic-1

Reporting Currency: USD

Prime System: All

Requirement Priority : All

Requirement Category : All

Requirements Included: All

| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|-----------------------------|------------------------------------------------------------|-------------------------|------------------------------------------------|----------------|-------------|-------------|--------|--------------------------------------------------|---------------------|
| 1- Currently Critical | Carpeting 3 - Carpet Broadloom - D Wing Lecture Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2015 | Sep 4, 2015 | | Open | Carpeting 3 - Carpet Broadloom - D Wing Lecture | 62,630 |
| 1- Currently Critical | Exterior Stairs - Concrete - Circular Renewal | Beyond Useful Life | B1015 - Exterior Stairs and Fire Escapes | 2015 | Sep 4, 2015 | | Open | Exterior Stairs - Concrete - Circular | 24,394 |
| 1- Currently Critical | DDC/Pneumatic System - Hybrid Renewal | Beyond Useful Life | D3060 - Controls and Instrumentation | 2015 | Sep 4, 2015 | | Open | DDC/Pneumatic System - Hybrid | 1,793,969 |
| 1- Currently Critical | Chiller - Centrifugal wo Cooling Tower - 1968 Renewal | Beyond Useful Life | D3030 - Cooling Generating Systems | 2015 | Sep 4, 2015 | | Open | Chiller - Centrifugal wo Cooling Tower - 1968 | 239,626 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|-------------------------------|-------------------------------------------------------|-------------------------|--------------------------------------------------|----------------|-------------|-------------|--------|--------------------------------------------------|---------------------|
| 1- Currently Critical | Motor Control Center Renewal | Beyond Useful Life | D3069 - Other Controls and Instrumentation | 2015 | Sep 4, 2015 | | Open | Motor Control Center | 328,911 |
| 1- Currently Critical | Steel Windows Renewal | Beyond Useful Life | B2020 - Exterior Windows | 2015 | Sep 4, 2015 | | Open | Steel Windows | 620,093 |
| 1- Currently Critical | Carpeting 3 - Carpet Broadloom - E Wing Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2015 | Sep 4, 2015 | | Open | Carpeting 3 - Carpet Broadloom - E Wing | 8,284 |
| 1- Currently Critical | Carpeting 3 - Carpet Broadloom - L Wing Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2015 | Sep 4, 2015 | | Open | Carpeting 3 - Carpet Broadloom - L Wing | 329,519 |
| 1- Currently | v Critical | | | | | | | | 3,407,426 |
| 2- Potentially Critical | Branch Wiring, Original - Equipment & Devices Renewal | Beyond Useful Life | D5021 - Branch Wiring Devices | 2015 | Oct 2, 2015 | | Open | Branch Wiring, Original - Equipment & Devices | 973,053 |
| 2- Potentially Critical | Aluminum Windows - L Wing Renewal | Beyond Useful Life | B2020 - Exterior Windows | 2015 | Oct 2, 2015 | | Open | Aluminum Windows - L Wing | 430,800 |
| 2- Potentially Critical | Heat Exchanger - HW/HW - Shell and Tube Renewal | Beyond Useful Life | D2020 - Domestic Water Distribution | 2015 | Oct 2, 2015 | | Open | Heat Exchanger - HW/HW - Shell and Tube | 4,717 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|-------------------------------|----------------------------------------------------|-------------------------|----------------------------------------------------|----------------|-------------|-------------|--------|--------------------------------------------|---------------------|
| 2- Potentially Critical | VCT 2 - S Wing Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2015 | Oct 2, 2015 | | Open | VCT 2 - S Wing | 3,166 |
| 2- Potentially Critical | Fire Alarm System - Average Density Renewal | Beyond Useful Life | D5037 - Fire Alarm Systems | 2015 | Oct 2, 2015 | | Open | Fire Alarm System - Average Density | 1,355,225 |
| 2- Potentially Critical | Public Address System - Average Density Renewal | Beyond Useful Life | D5031 - Public Address and Music Systems | 2015 | Oct 2, 2015 | | Open | Public Address System - Average Density | 26,736 |
| 2- Potentially Critical | Exit Signs, Original - Low Density Renewal | Beyond Useful Life | D5092 - Emergency Light and Power Systems | 2015 | Oct 2, 2015 | | Open | Exit Signs, Original - Low Density | 87,419 |
| 2- Potentially Critical | Carpeting 3 - Carpet Broadloom - C Wing Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2015 | Oct 2, 2015 | | Open | Carpeting 3 - Carpet Broadloom - C Wing | 109,892 |
| 2- Potentially Critical | ACT Concealed Spline System - D Wing Renewal | Beyond Useful Life | C3030 - Ceiling Finishes | 2016 | Sep 3, 2016 | | Open | ACT Concealed Spline System - D Wing | 13,041 |
| 2- Potentially Critical | ACT Concealed Spline System - A Wing Renewal | Beyond Useful Life | C3030 - Ceiling Finishes | 2016 | Sep 4, 2016 | | Open | ACT Concealed Spline System - A Wing | 60,718 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|-------------------------------|------------------------------------------------------|-------------------------|----------------------------------------------------|----------------|-------------|-------------|--------|--------------------------------------------|---------------------|
| 2- Potentially Critical | Carpeting 3 - Carpet Broadloom - S Wing Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2016 | Sep 4, 2016 | | Open | Carpeting 3 - Carpet Broadloom - S Wing | 97,921 |
| 2- Potentially Critical | UPS System 120V Single Phase - per KVA Renewal | Beyond Useful Life | D5092 - Emergency Light and Power Systems | 2016 | Sep 3, 2016 | | Open | UPS System 120V Single Phase - per KVA | 62,324 |
| 2- Potentially Critical | ACT Concealed Spline System - S Wing Renewal | Beyond Useful Life | C3030 - Ceiling Finishes | 2016 | Sep 4, 2016 | | Open | ACT Concealed Spline System - S Wing | 109,141 |
| 2- Potentially Critical | Central AHU - Const Volume w/Distribution Renewal | Beyond Useful Life | D3040 - Distribution Systems | 2015 | Oct 2, 2015 | | Open | Central AHU - Const Volume w/Distribution | 3,952,850 |
| 2- Potentially Critical | Perimeter Units Renewal | Beyond Useful Life | D3040 - Distribution Systems | 2015 | Oct 2, 2015 | | Open | Perimeter Units | 4,791,604 |
| 2- Potentially Critical | Emergency Battery Pack Lights Renewal | Beyond Useful Life | D5092 - Emergency Light and Power Systems | 2015 | Oct 2, 2015 | | Open | Emergency Battery Pack Lights | 12,251 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|-----------------------------------------------------------|-------------------------|---------------------------------------|----------------|--------------|-------------|--------|---------------------------------------------------|---------------------|
| 2- Potentially Critical | Boiler HW - Gas/Oil Fired w/Redundancy Renewal | Beyond Useful Life | D3020 - Heat Generating Systems | 2015 | Oct 2, 2015 | • | Open | Boiler HW - Gas/Oil Fired w/Redundancy | 169,417 |
| 2- Potentially Critical | ACT Concealed Spline System - L Wing Renewal | Beyond Useful Life | C3030 - Ceiling Finishes | 2016 | Sep 4, 2016 | | Open | ACT Concealed Spline System - L Wing | 328,167 |
| 2- Potential | ly Critical | | | | | | | | 12,588,442 |
| 3- Necessary - Not Yet Critical | Carpeting 3 - Carpet Broadloom - B Wing - 2000 Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2018 | Sep 4, 2018 | | Open | Carpeting 3 - Carpet Broadloom - B Wing - 2000 | 212,411 |
| 3- Necessary - Not Yet Critical | Fixed Theater Seating - Deluxe - S Wing Renewal | Beyond Useful Life | E - Equipment and Furnishings | 2018 | Sep 4, 2018 | | Open | Fixed Theater Seating - Deluxe - S Wing | 2,070 |
| 3- Necessary - Not Yet Critical | GWB Walls - Standard (Non-Painted) Renewal | Beyond Useful Life | C1010 - Partitions | 2018 | Nov 17, 2018 | | Open | GWB Walls - Standard (Non-Painted) | 471,155 |
| 3- Necessary - Not Yet Critical | Plaster Walls - 3 Coats Renewal | Beyond Useful Life | C1010 - Partitions | 2018 | Nov 17, 2018 | | Open | Plaster Walls - 3 Coats | 1,120,742 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|-----------------------------------------------------------------|--------------------------|-------------------------------------------|----------------|--------------|-------------|--------|---------------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | VAT - S Wing | Asbestos | C3020 - Floor Finishes | 2015 | Oct 1, 2015 | | Open | VCT 2 - S Wing | 5,531 |
| 3- Necessary - Not Yet Critical | Restroom - Complete - Gang - L Wing Renewal | Beyond Useful Life | C10 - Interior Construction | 2018 | Sep 4, 2018 | | Open | Restroom - Complete - Gang - L Wing | 168,440 |
| 3- Necessary - Not Yet Critical | HVAC Cost Study- Engineer Environmental and Efficiency Study | Air and Water Quality | D3040 - Distribution Systems | 2015 | Oct 1, 2015 | | Open | Central AHU - Const Volume w/Distribution | 60,349 |
| 3- Necessary - Not Yet Critical | Water Heater - Gas Renewal | Beyond Useful Life | D2020 - Domestic Water Distribution | 2015 | Nov 17, 2015 | | Open | Water Heater - Gas | 5,410 |
| 3- Necessary - Not Yet Critical | Roof Drainage Renewal | Beyond Useful Life | D2040 - Rain Water Drainage | 2018 | Nov 17, 2018 | | Open | Roof Drainage | 613,715 |
| 3- Necessary - Not Yet Critical | Carpeting 3 - Carpet Broadloom - B Wing - 2008 Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2018 | Nov 17, 2018 | | Open | Carpeting 3 - Carpet Broadloom - B Wing - 2008 | 14,912 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|-----------------------------------------------------|-------------------------|------------------------------------------------|----------------|--------------|-------------|--------|---------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | VCT 2 - C Wing Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2017 | Oct 2, 2017 | | Open | VCT 2 - C Wing | 77,338 |
| 3- Necessary - Not Yet Critical | CMU Walls - Glazed 2 Sides Renewal | Beyond Useful Life | C1010 - Partitions | 2018 | Nov 17, 2018 | | Open | CMU Walls - Glazed 2 Sides | 43,346 |
| 3- Necessary - Not Yet Critical | Exterior Stairs - Concrete Renewal | Beyond Useful Life | B1015 - Exterior Stairs and Fire Escapes | 2018 | Nov 17, 2018 | | Open | Exterior Stairs - Concrete | 24,840 |
| 3- Necessary - Not Yet Critical | Overhead Doors (Manually Operated) - B Wing Renewal | Beyond Useful Life | B2030 - Exterior Doors | 2018 | Sep 4, 2018 | | Open | Overhead Doors (Manually Operated) - B Wing | 20,828 |
| 3- Necessary - Not Yet Critical | Exhaust System - Kitchen Renewal | Beyond Useful Life | D3040 - Distribution Systems | 2018 | Nov 17, 2018 | | Open | Exhaust System - Kitchen | 56,342 |
| 3- Necessary - Not Yet Critical | Natural Gas Supply for Bldg Renewal | Beyond Useful Life | D2090 - Other Plumbing Systems | 2018 | Nov 17, 2018 | | Open | Natural Gas Supply for Bldg | 622,173 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|-----------------------------------------------------------|-------------------------|----------------------------------------------------|----------------|--------------------|-------------|--------|---------------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | Exterior Stairs - Concrete - Platform Renewal | Beyond Useful Life | B1015 - Exterior Stairs and Fire Escapes | 2018 | Nov 17, 2018 | | Open | Exterior Stairs - Concrete - Platform | 26,538 |
| 3- Necessary - Not Yet Critical | Emergency Generator - Lacks Capacity | Capacity/ Design | D5092 - Emergency Light and Power Systems | 2015 | Oct 1, 2015 | | Open | Emergency Generator - Average 100KW | 50,172 |
| 3- Necessary - Not Yet Critical | VCT 2 - A Wing Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2017 | Oct 2, 2017 | | Open | VCT 2 - A Wing | 528 |
| 3- Necessary - Not Yet Critical | VCT 2 - E Wing Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2017 | Oct 2, 2017 | | Open | VCT 2 - E Wing | 13,193 |
| 3- Necessary - Not Yet Critical | Custodial/Utility Sinks Renewal | Beyond Useful Life | D2010 - Plumbing Fixtures | 2015 | Sep 10, 2015 | | Open | Custodial/Utility Sinks | 151,031 |
| 3- Necessary - Not Yet Critical | Carpeting 3 - Carpet Broadloom - D Wing - 2000 Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2018 | Sep 4, 2018 | | Open | Carpeting 3 - Carpet Broadloom - D Wing - 2000 | 20,297 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|-----------------------------------------------------------|-------------------------|---------------------------------|----------------|--------------|-------------|--------|---------------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | Door Assembly - 6 x 7 Storefront Renewal | Beyond Useful Life | B2030 - Exterior Doors | 2018 | Oct 2, 2018 | | Open | Door Assembly - 6 x 7 Storefront | 115,348 |
| 3- Necessary - Not Yet Critical | Carpeting 3 - Carpet Broadloom - A Wing - 2000 Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2018 | Sep 4, 2018 | | Open | Carpeting 3 - Carpet Broadloom - A Wing - 2000 | 51,363 |
| 3- Necessary - Not Yet Critical | Water Coolers - Wall Mount Renewal | Beyond Useful Life | D2010 - Plumbing Fixtures | 2016 | Oct 2, 2016 | | Open | Water Coolers - Wall Mount | 21,080 |
| 3- Necessary - Not Yet Critical | Restroom - Complete - Gang - C Wing Renewal | Beyond Useful Life | C10 - Interior Construction | 2017 | Oct 10, 2017 | | Open | Restroom - Complete - Gang - C Wing | 168,440 |
| 3- Necessary - Not Yet Critical | Door Assembly - 3 x 7 HM Renewal | Beyond Useful Life | B2030 - Exterior Doors | 2018 | Oct 2, 2018 | | Open | Door Assembly - 3 x 7 HM | 64,909 |
| 3- Necessary - Not Yet Critical | Door Assembly - 6 x 7 HM Renewal | Beyond Useful Life | B2030 - Exterior Doors | 2018 | Oct 2, 2018 | | Open | Door Assembly - 6 x 7 HM | 22,427 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|----------------------------------------------------------|-------------------------|----------------------------------|----------------|--------------|-------------|--------|--------------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | Paint Masonry/Epoxy Finish - Economy Renewal | Beyond Useful Life | C3010 - Wall Finishes | 2015 | Nov 17, 2015 | | Open | Paint Masonry/Epoxy Finish - Economy | 65,126 |
| 3- Necessary - Not Yet Critical | Fixed Theater Seating - Deluxe - D Wing Renewal | Beyond Useful Life | E - Equipment and Furnishings | 2018 | Sep 4, 2018 | | Open | Fixed Theater Seating - Deluxe - D Wing | 15,452 |
| 3- Necessary - Not Yet Critical | Wet Standpipe System Renewal | Beyond Useful Life | D40 - Fire Protection | 2018 | Oct 2, 2018 | | Open | Wet Standpipe System | 583,068 |
| 3- Necessary - Not Yet Critical | Door Assembly - 3 x 7 Storefront Renewal | Beyond Useful Life | B2030 - Exterior Doors | 2018 | Oct 2, 2018 | | Open | Door Assembly - 3 x 7 Storefront | 27,452 |
| 3- Necessary - Not Yet Critical | Lighting Fixtures, Original - Average Density Renewal | Beyond Useful Life | D5022 - Lighting Equipment | 2017 | Oct 2, 2017 | | Open | Lighting Fixtures, Original - Average Density | 778,301 |
| 3- Necessary - Not Yet Critical | Kitchen Equipment Renewal | Beyond Useful Life | E - Equipment and Furnishings | 2017 | Oct 2, 2017 | | Open | Kitchen Equipment | 110,961 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|-------------------------------------------------------------------------------|-------------------------|------------------------------------------------|----------------|--------------|-------------|--------|-----------------------------------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | VAT - E Wing | Asbestos | C3020 - Floor Finishes | 2016 | Oct 1, 2016 | | Open | VCT 2 - E Wing | 3,974 |
| 3- Necessary - Not Yet Critical | Scoreboard Single Sided – College/High school Arena (Lower End) Renewal | Beyond Useful Life | D5031 - Public Address and Music Systems | 2017 | Oct 2, 2017 | | Open | Scoreboard Single Sided – College/High school Arena (Lower End) | 4,299 |
| 3- Necessary - Not Yet Critical | Carpeting 3 - Carpet Broadloom - B Wing Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2017 | Oct 2, 2017 | | Open | Carpeting 3 - Carpet Broadloom - B Wing | 15,740 |
| 3- Necessary - Not Yet Critical | Pedestrian Sky Bridges - Concrete Renewal | Beyond Useful Life | B2010 - Exterior Walls | 2018 | Nov 17, 2018 | | Open | Pedestrian Sky Bridges - Concrete | 864,833 |
| 3- Necessary - Not Yet Critical | Water Heater - Electric Renewal | Beyond Useful Life | D2020 - Domestic Water Distribution | 2015 | Nov 17, 2015 | | Open | Water Heater - Electric | 7,530 |
| 3- Necessary - Not Yet Critical | Drain Pipe: Not Insulated | Accessibility | D2030 - Sanitary Waste | 2015 | Jan 1, 2015 | | Open | Sanitary Waste | 1,558 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|-----------------------------------------------------------|-------------------------|---------------------------------------|----------------|--------------|-------------|--------|---------------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | Carpeting 3 - Carpet Broadloom - C Wing - 2008 Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2018 | Nov 17, 2018 | | Open | Carpeting 3 - Carpet Broadloom - C Wing - 2008 | 19,883 |
| 3- Necessary - Not Yet Critical | Quarry Tile - L Wing Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2018 | Sep 3, 2018 | | Open | Quarry Tile - L Wing | 69,980 |
| 3- Necessary - Not Yet Critical | Brick Walls - Mortar Joints Deteriorated | Reliability | B2010 - Exterior Walls | 2015 | Oct 1, 2015 | | Open | Brick Walls | 130,229 |
| 3- Necessary - Not Yet Critical | Dumbwaiter for Low Rise Renewal | Beyond Useful Life | D1090 - Other Conveying Systems | 2017 | Oct 2, 2017 | | Open | Dumbwaiter for Low Rise | 35,407 |
| 3- Necessary - Not Yet Critical | CMU Block Walls - Plain Renewal | Beyond Useful Life | C1010 - Partitions | 2018 | Nov 17, 2018 | | Open | CMU Block Walls - Plain | 109,826 |
| 3- Necessary - Not Yet Critical | GWB Taped and Finished - L Wing Renewal | Beyond Useful Life | C3030 - Ceiling Finishes | 2018 | Sep 4, 2018 | | Open | GWB Taped and Finished - L Wing | 5,074 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|-------------------------------------------------------------------------------------------|-------------------------|---------------------------------------------|----------------|--------------|-------------|--------|-----------------------------------------------------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | GWB Taped and Finished - D Wing Renewal | Beyond Useful Life | C3030 - Ceiling Finishes | 2018 | Sep 4, 2018 | | Open | GWB Taped and Finished - D Wing | 23,853 |
| 3- Necessary - Not Yet Critical | Hydraulic Freight Elevator Renewal | Beyond Useful Life | D1010 - Elevators and Lifts | 2016 | Nov 17, 2016 | | Open | Hydraulic Freight Elevator | 221,801 |
| 3- Necessary - Not Yet Critical | Distribution Equipment, Panelboards, and Feeders 13 - 4000A 480Y/277V & 208Y/120V Renewal | Beyond Useful Life | D5012 - Low Tension Service and Dist. | 2018 | Nov 17, 2018 | | Open | Distribution Equipment, Panelboards, and Feeders 13 - 4000A 480Y/277V & 208Y/120V | 1,282,236 |
| 3- Necessary - Not Yet Critical | Split System AC - 1990 Renewal | Beyond Useful Life | D3050 - Terminal and Package Units | 2015 | Nov 17, 2015 | | Open | Split System AC - 1990 | 18,959 |
| 3- Necessary - Not Yet Critical | Carpeting 3 - Carpet Broadloom - C Wing - 2000 Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2018 | Sep 4, 2018 | | Open | Carpeting 3 - Carpet Broadloom - C Wing - 2000 | 133,180 |
| 3- Necessary - Not Yet Critical | VAT - A Wing | Asbestos | C3020 - Floor Finishes | 2015 | Oct 1, 2015 | | Open | VCT 2 - A Wing | 951 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|-------------------------------------------------------------|-------------------------|------------------------------------|----------------|--------------|-------------|--------|-----------------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | Carpeting 3 - Carpet Broadloom - A Wing Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2015 | Sep 11, 2015 | | Open | Carpeting 3 - Carpet Broadloom - A Wing | 45,349 |
| 3- Necessary - Not Yet Critical | LAN System - Average Density Renewal | Beyond Useful Life | D5039 - Local Area Networks | 2016 | Nov 17, 2016 | | Open | LAN System - Average Density | 1,048,415 |
| 3- Necessary - Not Yet Critical | Hydraulic Passenger Elevator Renewal | Beyond Useful Life | D1010 - Elevators and Lifts | 2016 | Nov 17, 2016 | | Open | Hydraulic Passenger Elevator | 278,866 |
| 3- Necessary - Not Yet Critical | Painted Finish - (1 Coat Prime - 2 Coats Finish) Renewal | Beyond Useful Life | C3010 - Wall Finishes | 2018 | Sep 4, 2018 | | Open | Painted Finish - (1 Coat Prime - 2 Coats Finish) | 487,415 |
| 3- Necessary - Not Yet Critical | VAT - C Wing | Asbestos | C3020 - Floor Finishes | 2016 | Oct 1, 2016 | | Open | VCT 2 - C Wing | 212,519 |
| 3- Necessary - Not Yet Critical | Four Pipe Distribution System w/Pump Renewal | Beyond Useful Life | D3040 - Distribution Systems | 2018 | Nov 17, 2018 | | Open | Four Pipe Distribution System w/Pump | 5,619,614 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------------|--------------------------------------------------|-------------------------|----------------------------------------------------|----------------|--------------|-------------|--------|-----------------------------------------------------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | Sanitary Waste Renewal | Beyond Useful Life | D2030 - Sanitary Waste | 2018 | Nov 17, 2018 | | Open | Sanitary Waste | 1,901,597 |
| 3- Necessary - Not Yet Critical | Emergency Generator - Average 100KW Renewal | Beyond Useful Life | D5092 - Emergency Light and Power Systems | 2016 | Oct 12, 2016 | | Open | Emergency Generator - Average 100KW | 44,687 |
| 3- Necessary - Not Yet Critical | Unit Heaters - Hot Water Renewal | Beyond Useful Life | D3050 - Terminal and Package Units | 2016 | Oct 2, 2016 | | Open | Unit Heaters - Hot Water | 33,549 |
| 3- Necessary - Not Yet Critical | Restroom - Complete - Double - A Wing Renewal | Beyond Useful Life | C10 - Interior Construction | 2018 | Sep 4, 2018 | | Open | Restroom - Complete - Double - A Wing | 49,632 |
| 3- Necessar | y - Not Yet Critical | | | | | | | | 18,476,244 |
| Not Time Critical | Guards - Lacking | Grandfathered Code | | 2015 | Oct 17, 2015 | | Open | | 25,323 |
| Not Time Critical | Handrails - Lacking | Grandfathered Code | | 2015 | Oct 17, 2015 | | Open | | 19,690 |
| Not Time Critical | Electrical Panels - Lack Dedicated Space | Grandfathered Code | D5012 - Low Tension Service and Dist. | 2015 | Sep 11, 2015 | | Open | Distribution Equipment, Panelboards, and Feeders 13 - 4000A 480Y/277V & 208Y/120V | 26,733 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|----------------------|----------------------------------------------|-------------------------|----------------------------------|----------------|--------------|-------------|--------|--------------------------------------------------|---------------------|
| Not Time Critical | Guard and Handrails - Non-Compliant | Grandfathered Code | C20 - Stairs | 2016 | Oct 17, 2016 | | Open | Stairs | 283,405 |
| Not Time Critical | Electrical Outlets - Lack GFCI Receptacle | Grandfathered Code | D5021 - Branch Wiring Devices | 2015 | Oct 1, 2015 | | Open | Branch Wiring, Original - Equipment & Devices | 14,219 |
| Not Time Critical | Hardware - Not ADAAG Compliant | Accessibility | C1020 - Interior Doors | 2015 | Oct 17, 2015 | | Open | Swinging Doors | 525,545 |
| Not Time C | ritical | | | | | | | | 894,915 |
| Napier Acad | demic-1 | | | | | | | | 35,367,027 |





Region Name: Lake Michigan College

Campus Name: Lake Michigan College

Asset Name: South Haven-5

Reporting Currency: USD

Prime System: All

Requirement Priority : All

Requirement Category : All

Requirements Included: All

| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------|-------------------------------------------------|-------------------------|-------------------------------------------|----------------|--------------|-------------|--------|-----------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | Carpeting 5 - Carpet Tiles Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2018 | Sep 3, 2018 | | Open | Carpeting 5 - Carpet Tiles | 146,814 |
| 3- Necessary - Not Yet Critical | Security System - Light Density Renewal | Beyond Useful Life | D5038 - Security and Detection Systems | 2017 | Nov 17, 2017 | | Open | Security System - Light Density | 46,603 |
| 3- Necessary - Not Yet Critical | Vinyl Sheet Goods Renewal | Beyond Useful Life | C3020 - Floor Finishes | 2018 | Sep 3, 2018 | | Open | Vinyl Sheet Goods | 33,743 |
| 3- Necessary - Not Yet Critical | Paint Masonry/Epoxy Finish - Economy Renewal | Beyond Useful Life | C3010 - Wall Finishes | 2018 | Nov 17, 2018 | | Open | Paint Masonry/Epoxy Finish - Economy | 12,695 |
| 3- Necessary - Not Yet Critical | Fire Alarm System - Average Density Renewal | Beyond Useful Life | D5037 - Fire Alarm Systems | 2018 | Oct 2, 2018 | | Open | Fire Alarm System - Average Density | 184,284 |



| Priority | Requirement Name | Requirement Category | Prime System | Action Year | Action Date | Finish Date | Status | Linked System | Requirement Cost |
|------------------------------------|---------------------------------------------------------------|-------------------------|----------------------------------------|----------------|--------------|-------------|--------|-------------------------------------------------------------|---------------------|
| 3- Necessary - Not Yet Critical | Painted Finish - (1 Coat Prime - 2 Coats Finish) Renewal | Beyond Useful Life | C3010 - Wall Finishes | 2018 | Sep 3, 2018 | ` | Open | Painted Finish - (1 Coat Prime - 2 Coats Finish) | 69,563 |
| 3- Necessary - Not Yet Critical | DX Condensing Unit Renewal | Beyond Useful Life | D3030 - Cooling Generating Systems | 2018 | Nov 17, 2018 | | Open | DX Condensing Unit | 185,778 |
| 3- Necessary - Not Yet Critical | Unit Heaters - Electric Renewal | Beyond Useful Life | D3050 - Terminal and Package Units | 2018 | Nov 17, 2018 | | Open | Unit Heaters - Electric | 26,036 |
| 3- Necessary - Not Yet Critical | Folding Partitions Renewal | Beyond Useful Life | C1010 - Partitions | 2018 | Nov 17, 2018 | | Open | Folding Partitions | 114,176 |
| 3- Necessary - Not Yet Critical | Water Heater - Gas Renewal | Beyond Useful Life | D2020 - Domestic Water Distribution | 2018 | Nov 17, 2018 | | Open | Water Heater - Gas | 26,760 |
| 3- Necessary - Not Yet Critical | LAN System - Average Density Renewal | Beyond Useful Life | D5039 - Local Area Networks | 2018 | Nov 17, 2018 | | Open | LAN System - Average Density | 142,564 |
| 3- Necessary - Not Yet Critical | Fittings: Signage (Room Numbering and Identification) Renewal | Beyond Useful Life | C1035 - Identifying Devices | 2019 | Sep 3, 2019 | | Open | Fittings: Signage (Room Numbering and Identification) | 28,124 |
| 3- Necessary - N | 3- Necessary - Not Yet Critical | | | | | | | | |
| South Haven-5 | | | | | | | | 1,017,140 | |
| Lake Michigan College | | | | | | | | 58,919,069 | |
| Lake Michigan College | | | | | | | | 58,919,069 | |
| Summary | | | | | | | | | 58,919,069 |